

CITY OF DETROIT
SPECIAL PROVISION
FOR
CURB, REM, MODIFIED

1 of 1

DET: NH, MCS

Revised: 07-08-05

Description: This work consists of removing curb, whether separate or integral with the pavement, where the adjoining pavement remains. Where the curb is integral with the pavement, sawing will be required, Sawing and pavement, integral with the curb that is required to be removed, are included in the curb removal and will not be paid for separately. Removing curb shall also include earth excavation required for removing the existing curb.

When stone curb is removed, the removal shall also include the concrete backing located behind the curb and/or the concrete base on which the stone curb rests when removal is required to place the new curb. Removal of this concrete is included in the curb removal and will not be paid for separately,

Backfilling under the curb with granular material class II and behind the curb with selected excavated material (Such material shall be free from rubbish or debris, vegetable matter, large stones, concrete fragments, or other road material, lumber, tree roots, or branches. In general, selected excavated material to be suitable for backfill shall be restricted to sand or crumbly clay, (Blue clay is not considered a suitable backfill material), is included in the removal of the old curb and placing the new curb. If there is insufficient selected excavated material on the project, the contractor shall provide the needed fill material and no additional payment shall be received for providing this backfill.

The removal and replacement of curb adjacent to catch basins shall take place after the leveling course of HMA has been placed. The catch basin adjustment or reconstruction will take place concurrently with the adjacent curb work.

Lawn Sprinkler Systems, if encountered, shall be protected by the Contractor at no extra cost.

The work shall be in accordance with the applicable provisions of Section 204 of the 2003 MDOT Standard Specifications for Construction.

MEASUREMENT AND PAYMENT: The completed work as measured for Curb, Rem, Modified will be paid for at the contract unit price for the following item,

Pay Item

Pay Unit

Curb, Rem, Modified

Foot