

CITY OF DETROIT
SPECIAL PROVISION
FOR
CONSTRUCTION AT CAMPUS MARTIUS PARK
AND UNIT PAVERS

1 of 3

TYJT

2/24/09

GENERAL

When construction of any of the curb ramps at Campus Martius Park begins the Contractor shall notify the Detroit 300 Conservancy at least 3 calendar weeks before beginning work to coordinate activities.

Robert F. Gregory

President

Phone: (313) 962-0106

E-mail address: bgregory@detroit300.org

Heather Badrak

Business and Operations Manager

Phone: (313) 962-0112

E-mail address: hbadrak@detroit300.org

Detroit 300 Conservancy

One Campus Martius, 11th Floor

Detroit, Michigan 48226

Phone: (313) 962-0101

Fax Number: (313) 962-0114

MATERIALS

CONCRETE SURFACES

The concrete surfaces in the Park shall be paid for as "Sidewalk, Conc., ____ inch, Modified".

CONCRETE BASE COURSES

The new concrete base course for the pavers shall be paid for as Sidewalk, Conc, __ inch, Modified.

CITY OF DETROIT
SPECIAL PROVISION
FOR
CONSTRUCTION AT CAMPUS MARTIUS PARK
AND UNIT PAVERS

2 of 3

TYJT

2/24/09

UNIT PAVER MATERIALS

New Unit Paver Materials, to replace existing ones that are damaged, shall be as described in the Special Provision for “Unit Pavers, Materials”.

SUB-CONTRACTOR QUALIFICATIONS

The sub-contractor selected to do regarding of ramps, landings, and transitions with the pavers shall be an experienced unit pavers installation firm. The firm shall have completed work similar in material, design and extent to that indicated for the Project with a record of successful in-service performance. The firm shall have completed a minimum of five projects within the last three years that meet this requirement and shall upon request provide references for verification of successful performance.

DESCRIPTION

The work shall consist of removing existing unit pavers at locations shown on the plans and removing all materials down to the new sub-base elevations and re-pouring of the base slab and placement of the salvaged or new unit pavers to the new grades as shown on the plans.

INSTALLATION

A new concrete base course after the new sub-grade has been achieved and thoroughly compacted. Pavers shall be placed with a minimum joint width of 1/16” to a maximum of 1/8”. The joints should then be swept with dry sand to fill the joints. Existing Unit pavers, in the areas to be regarded, shall be carefully removed and stockpiled for reinstallation. Existing Unit Pavers that are damaged shall be replaced with the unit pavers purchased by the contractor under the Special Provision for “Unit Pavers, Materials”. Any Unit Pavers that are damaged by the contractor shall be replaced by him at no cost to the City.

CITY OF DETROIT
SPECIAL PROVISION
FOR
CONSTRUCTION AT CAMPUS MARTIUS PARK
AND UNIT PAVERS

3 of 3

TYJT

2/24/09

METHOD OF MEASUREMENT AND BASIS OF PAYMENT

The work shall be measured in square feet and shall include all materials, labor and equipment to reconstruct, with new or salvaged unit pavers, in the designated unit paver areas, to new grades, including placement of joints, placement of joints and dowels as shown on the plans. Materials, as a minimum, include removal of existing pavers, setting beds, and base slabs and the placement of new base slabs, setting beds and pavers (either new or salvaged).

PAY ITEM

PAY UNIT

Unit Pavers

Square Foot