

CITY OF DETROIT
SPECIAL PROVISION
FOR
RELOCATE/RESET MAIL BOX

1 of 1

TYJT

3/26/09

DESCRIPTION

Temporarily move and then relocate or reset a mail box as needed for installation of new curb ramps.

CONSTRUCTION

Prior to construction the contractor shall establish a survey reference point and obtain the necessary measurements to reinstall the mail box in its original location unless the plans indicate a new location for the mail box.

Existing mail boxes shall be protected and moved to a suitable location on site only when necessary for constructing proposed sidewalk as indicated on the plans. Mail boxes shall not be placed where they may hinder access to existing; doors, building entrances, fire doors, fire escapes, driveway approaches, alleys, fire hydrants, pedestrian access routes, or other existing pedestrian features. Any mail box moved in such a manner shall be protected for the duration of construction operations and returned to its original location after construction, unless shown otherwise on the plans.

When mail boxes are moved to a temporary location they shall be expansion bolted to the existing sidewalk and when they are placed in their final location, after construction of the curb ramps, they shall be expansion bolted to the surface with galvanized bolts. The temporary bolts shall be removed and the holes patched with grout.

METHOD OF MEASUREMENT AND BASIS OF PAYMENT

Work, materials and all other miscellaneous costs incurred while performing the work - including mounting hardware, equipment, hauling, and disposal - shall be included in the contract unit price and will not be paid for separately.

Pay Item

Unit

Relocate/Reset Mail Box

Each