			General	RAMP NUMBER																					TOTAL
				#1	#2	#3	#4	#5	#6	#8	#9	#11	#12	#13	#14	#15	# 16	# 17	#18	#19	#20	# 21	#34	# 35	#37	
ID	Description	Units																								
1000001	Mobilization, Max. ____	LS	1																							1
2040013	Sidewalk, Rem	Syd		147	107	233	90	187	218	210	116	218	52	177	148	217	50	199	171	153	65	106	49	90	138	3,139
2047001	Curb, Rem, Modified	Ft		156	88	279	95	161	179	182	127	184	33	153	146	159	64	209	148	100	73	36	32	108	145	2,859
2057021	Granular Material, Cl II, Modified	Cyd		6.0	3.0	20.0	4.0	18.0	25.0	7.0	5.0	7.0	2.0	18.0	6.0	7.0	2.4	8.0	6.0	5.0	3.0	3.0	2.0	4.0	6.0	167
4037050	Dr Structure Cover, Adj, Case 1, Modified	Ea			2	3		5	3		1	1	1			2	2		1	3	2	1	1	3		31
4037050	Dr Structure Cover, Adj, Case 2, Modified	Ea			2	4		4	5		2			4	2	3		5	3			2	1	2	4	43
4037050	Water Shutoff, Adj, Modified	Ea							1																	1
5020025	Hand Patching	Ton		2.9	1.6	9.9	2.0	8.0	11.0	3.4	2.4	3.5	1.0	8.0	3.0	3.0	1.2	3.9	2.7	2.4	1.5	1.5	0.7	2.0	2.8	79
5027011	HMA Surface, Rem, Modified	Syd		18	10	59	11	53	70	21	14	22	4	37	18	19	7	24	17	15	9	9	4	12	17	471
6027001	Integral Curb and Sidewalk, 2 Feet, Modified	Ft		60						91	78	90					46	105	104	92	58	32	7	61	76	899
8027001	Curb, Conc, Det E, Modified	Ft			84	217	53	44	32					51	43	79										603
8027010	Sidewalk, Conc, 4 inch, Modified	Sft		77	503	1,336	472	904	1,034	978	479	1,206	211	927	656	993	250	958	711	552	206	528	181	416	594	14,173
* **8027010**	**Sidewalk, ADA, Modified,**	**Sft**		**614**	**147**	**356**	**334**	**769**	**882**	**687**	**430**	**558**	**253**	**720**	**685**	**708**	**102**	**632**	**466**	**379**	**197**	**353**	**198**	**265**	**546**	**10,281**
8027050	24inx60in Detectable Warning Surface Tiles, Modified	Ea		8	4	12	4	8	8	8	6	8	2	8	8	8	2	8	8	6	4	6	2	4	8	140
8117001	Pavt Mrkg, Preformed Patterned, 12 inch, Zebra Crosswalk, Modified	Ft		644	806	977	748	1,188	1,232	660	280	1,339	352	1,056	1,100	1,100	130	500	960	1,156	574	285	60	271	990	17,447
8117001	Pavt Mrkg, Preformed Patterned, 24 inch, Stop Bar, Modified	Ft		76	115	136	65	86	76	77	48	143	24	74	80	80	20	77	89	115	62	47	16	55	74	1,755
8120050	Minor Traf Devices	LS	1																							1
8127050	Sign and Post Removal and Replacement	Ea				1		1		1	1	1					1		1	1		1		1		10

* WHEREVER THE PAY ITEM "Sidewalk, ADA, Modified" APPEARS IN THIS PART B OF THESE DOCUMENTS, IT SHALL BE UNDERSTOOD TO MEAN THE PAY ITEM FOR "Sidewalk Ramp, ADA, 6 inch, Modified".

LEGEND

SIDEWALK, CONC., 4 INCH. MODIFIED
HAND PATCHING
JOINT LINE
SCORING LINE

MANHOLE
CATCH BASIN
GATE VALVE & WELL
WATER SHUT OFF VALVE
FIRE HYDRANT
HAND HOLE
ELECTRIC RISER OR METER
TELEPHONE RISER
CABLE TV RISER

UTILITY POLE
UTILITY POLE W/ LAMP EXTENSION (ARROW INDICATES DIRECTION OF ARM)
LIGHT POLE
LIGHT POLE WITH LAMP EXTENSION
TRAFFIC SIGNAL
POLE WITH TRAFFIC SIGNAL (OVER ROAD)
GROUND LEVEL OR DECORATIVE LIGHTING
FLAG POLE

PHONE OR PHONE BOOTH
CHAIN LINK FENCE (C.L.)
GUARD RAIL
METAL OR CONC. POST
MAILBOX
SIGN
PARKING METER
BENCH — BENCH

PROPERTY LINES
SDA#10 — TRAVERSE POINT
AREAWAYS
555.55 — SPOT ELEVATION
TC — TOP OF CURB ELEVATION
G — GUTTER ELEVATION
TP — TOP OF PAVEMENT ELEVATION
EM — EDGE OF METAL ELEVATION
TW — TOP OF WALK ELEVATION
WALL — TOP OF WALL ELEVATION
GR — GROUND ELEVATION
CONC. — CONCRETE
ASPH. — ASPHALT
L.S. — LANDSCAPED
F.F. — FINISH FLOOR ELEVATION
D.L. — DOOR LEDGE ELEVATION

BENCHMARK DESCRIPTIONS

BM#28-353A FOUND CITY OF DETROIT CONTROL DISK IN MONUMENT BOX IN SIDEWALK AT THE NORTHEAST CORNER OF FORT STREET AND WASHINGTON BLVD. ELEV.=127.85

SITE BM#11 ARROW ON HYDRANT LOCATED ON THE NORTHWEST CORNER OF WOODWARD AVENUE AND CLIFFORD STREET. ELEV.=121.65

Spalding DeDecker Associates, Inc.

Engineering Consultants
Infrastructure • Land Development • Surveying

220 W. Congress, Suite 400
Detroit, MI 48226
Phone: (313) 967-4700
Fax: (313) 967-4707

905 South Blvd. East
Rochester Hills, MI 48307
Phone: (248) 844-5400
Fax: (248) 844-5404

2505 W. Jefferson
Trenton, MI 48183
Phone: (734) 671-4344
Fax: (734) 671-4347

www.spaldingdedecker.com

DDA CITY OF DETROIT
DOWNTOWN DEVELOPMENT AUTHORITY
500 Griswold, Suite 2200,
Detroit, MI 48228
P: (313) 963-2940
F: (313) 963-8893

3 WORKING DAYS
BEFORE YOU DIG CALL MISS DIG.
1-800-482-7171
For free location of public utility lines

NOTE: UTILITY INFORMATION ON THIS DRAWING MAY BE FROM INFORMATION DISCLOSED TO THIS FIRM BY THE VARIOUS UTILITY COMPANIES, CITY/COUNTY AGENCIES AND OTHER VARIOUS SOURCES. UNDERGROUND UTILITIES WHICH ARE ON PRIVATE PROPERTY ARE USUALLY NOT DELINEATED UPON A UTILITY COMPANY'S PUBLISHED PLANS. THEIR LOCATION, IF SHOWN UPON THIS SURVEY, ARE APPROXIMATED FROM FOUND PAINT MARKS/STAKES, ETC. AS LOCATED BY THIS FIRM FROM SOURCES WHICH ARE UNKNOWN. NO GUARANTEE IS GIVEN AS TO THE COMPLETENESS OR ACCURACY THEREOF.

PRIOR TO CONSTRUCTION, ALL LOCATIONS AND DEPTHS OF EXISTING UTILITIES (IN CONFLICT WITH PROPOSED IMPROVEMENTS) SHALL BE VERIFIED IN THE FIELD. CALL MISS DIG 3 WORKING DAYS PRIOR TO CONSTRUCTION.

COPYRIGHT © 2007 SPALDING DeDECKER ASSOCIATES, INC. THIS DRAWING AND THE SUBJECT MATTER CONTAINED THEREON IS PROPRIETARY AND IS NOT TO BE USED OR REPRODUCED WITHOUT WRITTEN PERMISSION OF SPALDING DeDECKER ASSOCIATES, INC.

ADA RAMP DESIGN
QUANTITIES SHEET

SECTION PRIVATE CLAIM
TOWN RANGE
CITY OF DETROIT
WAYNE COUNTY

NO.	DATE	REVISION

SHEET NO. 068

DRAFTER	DATE 07-09-09
DESIGNER MT	DATE 09-04-07
CHECKED	DATE
PROJECT MANAGER M. HAMOOD	BID PLAN DATE
DEPARTMENT MANAGER APPROVAL	DATE

VERIFY SCALES
BAR IS ONE INCH ON ORIGINAL DRAWING
IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY

JOB NO. DE06001_OT	DRAWING NO. DE06001ADA-Q1
SCALE: N/A	SHEET NO. Q-1

S:\11\DE06001_OT\dwg\ADA RAMPS-Q\DE06001ADA-Q1.dwg 7/8/2009 10:00:59 AM EDT