

CITY OF DETROIT
SPECIAL PROVISION
FOR
DRAINAGE COMPOSITE

1 of 1

TYJT

2/24/09

Description

The work consists of the placement of a composite drainage mat on top of the waterproofing membrane to facilitate sub-surface drainage when areaway roofs have been replaced.

Materials:

The drainage composite shall be J-Drain 300, CCW Miradrain 9000, Terram 1C1, or an approved equivalent.

Construction:

Construction and installation shall be strict accordance with the manufacturers printed recommendations.

Method of Measurement and Basis of Payment

Work, labor, materials and all other miscellaneous costs incurred while performing the work shall be included in the contract unit price and will not be paid for separately.

Pay Item

Unit

Drainage Composite

Square Feet