#### TITLE SHEET GENERAL PLAN OF SITE LOG OF BORINGS GENERAL PLAN OF STRUCTURE MISCELLANEOUS DETAILS PRECAST CULVERT SPECIFICATIONS

STEEL REINFORCEMENT AND QUANTITES

RIVERSIDE AVE. INDEX OF SHEETS

# CITY OF DETROIT DENNIS W. ARCHER-MAYOR CITY ENGINEERING DIVISION DEPARTMENT OF PUBLIC WORKS





PLANS FOR PROPOSED


REFLACEMENT OF THE RIVERSIDE AVE. BRIDGE OVER CANAL (BW-242), FEDERAL STRUCTURE NO. 0108300B02


#### MOOT STANDARD PLANS

LIGHTED ARROWS AND BARRICADES	R-12
SOIL EROSION AND SEDIMENTATION CONTROL MEASURES	હિ−96
SEEDING AND SODDING	R -100
NOLDING, BEVEL, LIGHT STANDARD ANCHOR BOLT ASSEMBLY AND NAME PLATE DETAILS	B-10
BRIDGE RAILING. SOLID PARAPET TYPE	E-18
BRIDGE RAILING. 1 TUBE	B -24

#### CITY OF DETROIT STANDARD PLANS (3-7-98)

TYPE	IIIF	RINTEGRA	AL CUR	}		( -438	(
TYPIC	CAL F	PAVEMENT	CROSS	SECTION		C-438	4





THE DESIGN OF THIS STRUCTURE IS BASED ON CURRENT AASHTO STANDARD SPECIFICATIONS FOR HIGHWAY BRIDGES MS18 LOADING. LIVE LOAD PLUS IMPACT DEFLECTION DOES NOT EXCEED 1/1000 OF THE SPAN LENGTH. THE

EXCEPT WHERE OTHERWISE INDICATED ON THESE PLANS, THE PROPOSAL, AND SUPPLEMENTAL SPECIFICATIONS CONTAINED HEREIN, ALL MATERIALS AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE MICHIGAN DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR CONSTRUCTION 1996

TO THE DESIGN OFFICE IN DETROIT. AND THE STRUCTURE SHALL BE STAKED OUT USING THE ACTUAL INTERSECTION OF THE CENTERLINE OF THE BRIDGE AND ROADWAY

ALL EXPOSED CONCRETE CORNERS SHOWN SQUARE ON THE PLANS SHALL BE BEVELED WITH 13 mm TRIANGULAR MOLDINGS EXCEPT AS OTHERWISE NOTED.

THE DESIGN OF THE STRUCTURAL MEMBERS IS BASED ON MATERIAL OF THE FOLLOWING GRADES AND STRESSES.

CONCRETE: GRADE S2 CONCRETE: GRADE D STEEL REINFORCEMENT:

f'c = 21 MPaf'c = 28 MPafy = 400 MPa

ALL DIMENSIONS ON THESE PLANS ARE IN MILLIMETERS EXCEPT AS NOTED.

#### PROJECT:


REMOVAL AND REPLACEMENT OF THE STRUCTURES AT RIVERSIDE AVE. OVER

IN THE CITY OF DETROIT.

CONTRACT PW-6869R

PLANS PREPARED BY SNELL ENVIRONMENTAL GROUP. INC.

CITY ENGINEERING DIVISION



RECOMMENDED FOR APPROVAL RECOMMENDED FOR APPROVAL APPROVED

12/15/99 DATE

DATE

**APPROVED** 


DRWG. NO.

SCALE NOT TO SCALE 9641-5160-01 SHEET 1 OF 8

METRIC

CURVE AND ALIGNMENT DATA ARE IN METERS. STATIONS ARE IN KILOMETERS + METERS.

3	S	Annual company of the	SUPPLIES AND DESCRIPTION OF THE PARTY OF THE	Control of the Control of the Control
Marin Marin	W	DSCN BY	M.A.M.	5-97
The state of the s	2	DR'N BY	R.J.D.	5-97
	w	CK D BY	R.G.W.	5-97
	2000 2000	FINAL CK'D BY	M.D.W.	2-99
		APP'D BY		



ENVIRONMENTAL GROUP. INC. A DLZ Company
151 W. CONGRESS, SUITE 328 DETROIT, MICHIGAN 48226





OF DETROI MICHIGAN

RIVERSIDE AVE. OVER CANAL (BW-242)


Tris.


TITLE SHEET







h:\96415160.01\bridge\final\03bori Feb. 2, 1999 14:07:04













h:\96415160.01\bridge\final\06det. Feb. 2, 1999 14:48:23




#### STANDARD JOINT DETAIL





PROVIDE THIS THICKENED EDGE WHERE PROPOSED PAVEMENT MEETS EXIST. PAVEMENT

#### DETAIL OF THICKENED EDGE




### TYPE IIIR. INTEGRAL CURB





TYPICAL SIDEWALK. CONCRETE. 300 mm DETAIL

(TYPICAL ALL 4 QUADRANTS)



BRIDGE RAILING ELEVATION

NOTE:

DEWATERING SHALL BE INCLUDED IN PAY ITEM "STEEL SHEET PILING. TEMP. LEFT IN PLACE"

METRIC

DIMENSIONS ARE IN MILLIMETERS UNLESS
OTHERWISE SHOWN. ELEVATIONS, CCIORDINATES.
CURVE AND ALIGNMENT DATA ARE IN METERS.
STATIONS ARE IN KILOMETERS + METERS.

RIVERSIDE AVE. SNELL SCALE NOT TO SCALE MISCELLANEOUS ENVIRONMENTAL OF DETROIT 5-97 PROJECT OVER CANAL GROUP . INC . A DLZ Company 9641-5160-01 5-97 DETAILS MICHIGAN FINAL CK'D BY M.D.W. 151 W. CONGRESS, SUITE 328 2-99 (BW-242)SHEET DETROIT. MICHIGAN 48226 TELEPHONE (313) 961-4040 R6 OF 8 APP'D BY

## SPECIFICATIONS FOR MANUFACTURE AND INSTALLATION OF PRECAST CULVERT BRIDGE SYSTEMS

#### 1. DESCRIPTION

This work shall consist of constructing a Con/Span culvert or approved equalin accordance with these specifications and in reasonably close conformity with the lines, grades, design and dimensions shown on the plans or as established by the Engineer.

Precast reinforced concrete Con/Span culverts or approved equal manufactured in

accordance with this specification shall be designated by span

#### 3. MATERIALS - CONCRETE

The concrete for the culverts shall be air-entrained when installed in areas subject to freeze-thaw conditions, composed of portland cement, fine and course aggregates, admixtures and water. Concrete shall contain 6 ± 2 percent air. The air entraining admixture shall conform to AASHTO M154.

- 3.1. Cement Portland cement shall conform to the requirements of ASTM Specifications C150-Type I, Type II, or Type III cement.
- 3.2 Course Aggregate Shall consist of stone having a maximum size of 25 mm Aggregate shall meet requirements for ASTM C33.
- 3.3 Water Reducing Admixture The manufacturer may submit for approval by the Engineer, water-reducing admixture for the purpose of increasing workability and reducing the water requirement for the concrete.
- 3.4 Calcium Chloride The addition to the mix of calcium chloride or admixtures containing calcium chloride will not be permitted.

#### 4. MATERIALS - STEEL REINFORCEMENT AND HARDWARE

All reinforcing steel for the culverts shall be fabricated and placed in accordance with the detailed shop drawings submitted by the manufacturer.

4.1 Steel Reinforcement - Reinforcement shall consist of welded wire fabric conforming to ASTM Specification A 185 or A 497, or deformed billet steel bars conforming to ASTM Specification A 615, Grade 400. Longitudinal distribution reinforcement may consist of welded wire fabric or deformed billet-steel bars.

#### 5. MANUFACTURE

- 5.1 Mixture The aggregates, cement and water shall be proportioned and mixed in a batch mixer to produce a homogeneous concrete meeting the strength requirements of this specification. The proportion of portland cement in the mixture shall not be less than 256 kg (5 sacks) per cubic meter of concrete.
- 5.2 Curing The precast concrete culvert units shall be cured for a sufficient length of time so that the concrete will develop the specified compressive strength in 28 days or less. Any one of the following methods of curing or combinations thereof shall be
  - 5.2.1 Steam Curing The culverts may be low pressure, steam cured by a system that will maintain a moist atmosphere.
  - 5.2.2 Water Curing The culverts may be water cured by any method that will keep the sections moist.
  - 5.2.3 Membrane Curing A sealing membrane conforming to the requirements ASTM Specification C 309 may be applied and shall be left intact until the required concrete compressive strength is attained. The Concrete temperature at the time of application shall be within . 6 degree C of the atmospheric temperature. All surfaces shall be kept moist prior to the application of the compounds and shall be damp when the compound is applied.
- 5.3 Forms the forms used in manufacture shall be sufficiently rigid and accurate to maintain the culvert dimensions within the permissible variations given in Section 7. All casting surfaces shall be of smooth material.
- 5.4 Handling Handling devices or holes shall be permitted in each culvert for the purpose of handling and
- 5.5 Storage The culverts shall be stored in such a manner to prevent cracking or damage. The units shall not be stored in an upright position until the compressive strength is a minimum of 28 MPa.

#### 6. DESIGN

6.1 The culvert dimension and reinforcement details shall be as prescribed in the plan and the shop drawings provided by the manufacturer subject to the provisions of Section 7. The minimum concrete compressive strength shall be 28 MPa. The minimum steel yield strength shall be 400 MPa.

The culverts are designed in accordance with the "Standard Specifications for Highway Bridges" adopted by the American Association of State Highway and Transportation Officials, 1996; and the Alternate Military Loading. A minimum of 300 mm of cover above the crown of the culvert is required in the installed condition. (Unless noted otherwise and designed accordingly.)

- 6.2 Placement of Reinforcement The cover of concrete over the outside circumferential reinforcement shall be 50 mm minimum. The cover of concrete over the inside circumferential reinforcement shall be 40 mm minimum. The clear distance of the end circumferential wires shall not be less than 25 mm nor more than 50 mm from the ends of the culvert. Reinforcement shall be assembled utilizing single or multiple layers of welded wire fabric, or utilizing a single layer of deformed billet-steel bars. The welded wire fabric shall be composed of circumferential and longitudinal wires meeting the spacing requirements of 6.4 and shall contain sufficient longitudinal wires extending through the culvert to maintain the shape and position of reinforcement. Longitudinal distribution reinforcement may be welded wire fabric or deformed billet-steel bars and shall meet the spacing requirements of 6.4. The ends of the longitudinal distribution reinforcment shall be not more than 75 mm from the ends of the culvert.
- Bending of Reinforcement the outside and inside circumferential reinforcing steel for the corners of the culvert shall be bent to such an angle that is approximately equal to the configuration of the culvert's outside corner.
- 6.4 Laps, Welds, and Spacing Tension splices in the circumferential reinforcement shall be made by lapping. Laps may be tack welded together for assembly purposes. For smooth welded wire fabric, the overlap shall meet the requirements of ACI 12.8 and 12.19. For deformed welded wire fabric, the overlap shall meet the requirements of ACI 12.7 and 12.18. For deformed billet-steel bars, the overlap shall meet the requirements of ACI 12.2. For splices other than tension splices, the overlap shall be a minimum of 300 mm for welded wire fabric or deformed billet-steel bars The spacing center to center of the circumferential wires in a wire fabric sheet shall be not less than 50 mm nor more than 100 mm. For the wire fabric. the spacing center to center of the longitudinal wires shall not be more than 200 mm. The spacing center to center of the longitudinal distribution steel for either line of reinforcing in the top slab shall be not more than 400 mm.

#### 7. PERMISSIBLE VARIATIONS

- 7.1 Internal Dimensions The internal dimension shall vary not more than 1% from the design dimensions nor more than 40 mm whichever is less. The haunch dimensions shall vary not more than 20 mm from the design dimension.
- 7.2 Slab and Wall Thickness The slab and wall thickness shall not be less than that shown in the design by more than 6 mm. A thickness more than that required in the design shall not be cause for rejection.
- 7.3 Length of Opposite Surfaces Variations in laying lengths of two opposite surfaces of the culvert shall not be more than 16 mm in any culvert section, except where beveled ends for laying of curves are specified by the purchaser.
- 7.4 Length of Section The underrun in length of a section shall not be more than 13 mm in any culvert.
- 7.5 Position of Reinforcement The maximum variation in position of the reinforcement shall be ± 13 mm. n no case shall the cover over the reinforcement be less than 40 mm for the outside circumferential steel or be less than 25 mm for the inside circumferential steel as measured to the external or internal surface of the culvert. These tolerances or cover requirements do not apply to mating surfaces of the joints.
- 7.6 Area of Reinforcement The areas of steel reinforcement shall be the design steel areas as shown in the manufacturer's shop drawings. Steel areas greater than those required shall not be cause for rejection. The permissible variation in diameter of any reinforcement shall conform to the tolerances prescribed in the ASTM Specification for that type of reinforcement.

#### 8. TESTING AND INSPECTION

- 8.1 Type of Test Specimen Concrete compressive strength shall be determined from compression tests made on cylinders or cores. For cylinder testing a minimum of 4' cylinders shall be taken' during each production run. For core testing, one core shall be cut from a culvert section selected at random from each group of 15 culverts or less of a particular size and production run. For each continuous production run, each group of 15 culverts of a single size or fraction thereof shall be considered separately for the purpose of testing and acceptance. A production run shall be considered continuous if not interrupted for more than 3 consecutive days.
- 8.2 Compression Testing Cylinders shall be made and tested as prescribed by the ASTM C 39 Specification. Cores shall be obtained and tested for compressive strength in accordance with the provisions of the ASTM C 497 Specification.
- 8.3 Acceptability of Cylinder Tests Failure of any of the 28 day test cylinders to meet 90 percent of the minimum compressive strength requirement can be cause for
- 8.4 Acceptability of Core Tests The Compressive strength of the concrete in each group of culverts as defined in 8.1 is acceptable when the core test strength are equal to or greater than the design concrete strength. When the compressive strength of the core tested is less than the design concrete strength, the culvert from which that core was taken may be recored. When the compressive strength of the recore is equal to or greater than the design concrete strength, the compressive strength of the concrete in that group of culverts is acceptable.
  - 8.4.1 When the compressive strength of any recore is less than the design concrete strength, the culvert from which that core was taken shall be rejected. Two culverts from the remainder of the group shall be selected at random and one core shall be taken from each. If the compressive strength of both cores is equal to or greater than the design concrete strength, the compressive strength of the remainder of that group of culverts is acceptable. If the compressive strength of either of the two cores tested is less than the design concrete strength, the remainder of the group of culverts shall be rejected or, at the option of the manufacturer, each culvert of the remainder of the group shall be cored and accepted individually, and any of these culverts that have cores with less than the design concrete strength shall be rejected.
  - 8.4.2 Plugging Core Holes The core holes shall be plugged and sealed by the manufacturer in a manner such that the culvert will meet all of the test requirements of this specification. Culverts so sealed shall be considered satisfactory for use.
  - 8.4.3 Test Equipment Every manufacturer furnishing culverts under this specification shall furnish all facilities and personnel necessary to carryout the

#### 9. JOINTS

The culverts shall be produced with flat butt ends. The ends of the culvert shall be such that when the sections are laid together they will make a continuous line of culverts with a smooth interior free of appreciable irregularities, all compatible with the permissible variations in Section 7. The joint width shall not exceed 20 mm.

#### 10. WORKMANSHIP AND FINISH

The culverts shall be substantially free of fractures. The ends of the culverts shall be normal to the walls and centerline of the culvert section, within the limits of the variations given in Section 7, except where beveled ends are specified. The surface of the culverts shall be a smooth steel form or troweled surface. Trapped air pockets causing surface defects shall be considered as part of a smooth steel form finish.

#### 11. REPAIRS

Culverts may be repaired, if necessary, because of imperfections in manufacture or handling damage and will be acceptable if, in the opinion of the purchaser, the repairs are sound, properly finished and cured, and the repaired section conforms to the requirements of this specification.

#### 12. INSPECTION

The quality of materials, the process of manufacture, and the finished culverts shall be subject to inspection by the purchaser.

#### 13. REJECTION

Culverts shall be subject to rejection on account of any of the specification requirements. Individual culverts may be rejected because of any of the following.

- 13.1 Fractures or cracks passing through the wall, except for a single end crack that does not exceed one half the thickness of the wall.
- 13.2 Defects that indicate proportioning, mixing, and molding not in compliance with Section 5.
- 13.3 Honeycombed or open texture, and
- 13.4 Damaged ends, where such damage would prevent making a satisfactory joint.

#### 14. MARKING

Each culvert shall be clearly marked by waterproof paint. The following shall be shown on the inside of the vertical leg of the culvert section:

Culvert Section Span X Culvert Fise

Date of Manufacture

Name or trademark of the manufacturer

And in the case of headwall sections. east or west face shall also be marked

#### 15. CONSTRUCTION REQUIREMENTS

- 15.1 Footings the culverts shall be installed on either precast or cast-in-place concrete footings. The design size and elevation of the footers shall be as determined by the Engineer. A 75 mm deep keyway shall be formed in the top surface of the footing 75 mm lear of the outside faces of the culvert, unless specified otherwise on the plans. the footings shall be given a smooth float finish and shall reach a compressive strength of 14 MPa before placement of the culvert sections. The completed footing surface shall be constructed in accordance with grades shown on the plans. When tested with a 3000 mm straight edge, the surface shall not vary more than 6 mm in 3000 mm. If a precast concrete footer is used, the contractor shall prepare a 100 mm thick layer of compacted granular material the full width of the footer prior to stacing the precast footer.
- 15.2 Placement of the Culverts The culverts shall be placed as shown on the Engineer's plan drawings. Special care shall be taken in setting the culverts to the true line and grade. The culverts shall be set on 150 mm X 150 mm masonite or steel shims. A minimum of 13 mm que shall be provided between the footing and the bottom of the culvert's verticallegs. The gap shall be filled with cement grout (portland cement and water or cement mortar composed of one part portland cement and three parts of sand, by volume, and water.
- 15.3 External Protection of Joints The butt joint made by two adjoining. The completed work as measured for Precast Culvert culverts shall be covered with a 22 mm X 35 mm (32 mm round equivalent) piece of butyl rope and a minimum of 230 mm wide joint wrap. The surface shall be free of dirt before applying the joint material. A primer compatible with the joint wrap to be used shall be applied for a minimum width of 230 mm on each side of the joint. The external wrap shall be either EZ-WRAP RUBBER by PRESS-SEAL GASKET CORPORATION, SEAL WRAP by MAR MAC MANUFACTURING CO. Inc. or approved equal. The joint shall be covered continuously from the bottom of the culvert leg, across the top of the arch and to the opposite culvert section leg. Any laps that result in the loint wrap shall be a minimum of 150 mm long with the overlap running downhill.

In addition to the joints between units, the joint between the end unit and the headwall shall be sealed. If using precast wingwalls, the joint between the end bridge unit and the wingwall shall be sealed with this type of wrap or at the discretion of the Engineer, filter fabric shall be substituted.

During the backfilling operation, care shall be taken to keep the joint wrap in its proper location over the joint.

15.4 Backfill - Backfill shall be considered as all replaced excavation and new embankment adjacent to the Con/Span or approved equal bridge units and wingwalls. The project construction and material specifications which include the specifications for excavation for structures and roadway excavation and embankment construction shall apply except as modified in this section.

Backfill material for a minimum width of 1220 mm on each side of the culvert, from the base of the unit to 300 mm above the outside corner shall be a soil meeting AASHTO classification A1, A2, A3 or A4 unless authorization to use a different materials given in writing by the designer. For heights of fill over 3660 mm, only A1 & A3 materials shall be used. Maximum dry density shall be determined by AASHTO T-99 or other approved methods. Backfill shall be placed and compacted in layers untill the density is not less than 95% of maximum dry density. All material outside the backfill zone shall be good quality, well compacted embankment or in situ soil.

No backfill shall be placed against any structural elements until they have been approved by the Engineer.

Backfill against a waterproofed surface shall be placed carefully to avoid damage to the waterproofing material.

Mechanical tampers or approved compacting equipment shall be used to compact all backfill and embankment immediately adjacent to each side of the culvert and over the top of the culvert until it is covered to a minimum depth of 300 mm. The backfill within 1220 mm of each side of the culvert shall be placed in lifts of 200 mm or less (loose depth). Heavy compaction equipment shall not be operated in this area or over the culvert until it is covered to a depth of 300 mm

Lightweight dozers and graders may be operated over culverts having one 300 mm of compacted cover, but heavy earth moving equipment (larger than a D-4 Dozer weighing in excess of 107 kN and having track pressures of 55 kPa or greater) shall require 600 mm of cover unless the design cover is less than 600 mm. In no case shall equipment operating in excess of the design load (MS18 or MS23) is to be permitted over the culvert unless approved by Con\Span or approved equal.

Any additional fill and subsequent excavation required to provide this minimum cover shall be made at no additional cost to the project.

As a precaution against introducing unbalanced stresses in the culvert and wingwalls, when placing backfill at no time shall the difference between the heights of fill on opposite sides of the culvert exceed 600 mm.

Backfill in front of wingwalls shall be carried to ground lines shown in the plans.

#### 16. MEASUREMENT AND PAYMENT

will be paid for at the contract unit price for the following contract item (pay item).

Pay Item

Pay Unit

12802 x 4267 precast concrete three - sided box Culvert


Meter

Payment for Precast Culvert shall be payment in full for labor, equipment and material necessary to design, manufacture and install the arch elements, including any steel shims needed to level the arch elements, casting holes in the elements as needed for guardrail posts, casting in the anchor assembly per STD. B-18-B furnishing and placing the grout between the footing and the arch elements, precast headwall units, steel connection plates between units, and furnishing and placing the joint waterproofing.

#### METRIC

DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE SHOWN. ELEVATIONS, COORDINATES. CURVE AND ALIGNMENT DATA ARE IN METERS. STATIONS ARE IN KILOMETERS + METERS.

DSGN BY R.J.D. 5-97 R.G.W. 5-97 CK'D BY M.D.W. INAL CK'D BY 2-99 APP'D BY



SNELL ENVIRONMENTAL GROUP. INC. A DLZ Company 151 W. CONGRESS. SUITE 328 DETROIT, MICHIGAN 48226

TELEPHONE (313) 961-4040



CITY OF DETROIT MICHIGAN

RIVERSIDE AVE. OVER CANAL (BW-242)

PRECAST CULVERT SPECIFICATIONS

SCALE NOT TO SCALE PROJECT NO.

9641-5160-SHEET R7 OF 8

BAR		DIMENSIONS										NO.	TOTAL
D.I.I	6	ь	c	d	6	f	9	h	J	k	m	REO'D	MASS
A1601700	1700								<u>Parties de l'information de l'appression de l</u>			236	62.
A1605377	5377											56	46
A1607570	7570											56	65
		*****											
									The state of the s				
										-			
										The state of the s			
			art arene de la companya de la comp	estate de la constitución de la				CONTENT OF THE CONTENT OF THE PROPERTY OF					
EA1301650	1650									<u>      L_s</u>	UBTOTAL		1748
EA1304435	4435			et en proposite standarden et het en veter destronassiellen en							-	88	14
EA1313360												40	17
	13360	470				The state of the s						12	15
ED1902018**	940	138	940									64	28
										Milmilation de			
										· ·		Partition of the community of the	
ant the control of th												o The Principle and College of the Section of the S	
										Proposition of the second second		TO PROTECTION OF THE STREET WAS ASSESSED.	e de la composition della comp
				er en electrici de la companya de constitución de la constitución de la constitución de la constitución de la c								- andrew are representation to the second	
										en e			
												Nagaration and a second a second and a second a second and a second a second and a second and a second and a	
										E y traction de la company de la company La company de la company de			
	To your report of the first of the second of	NOTES OF THE STREET OF THE STR											
1	I		1		1		1	1	1		1	1	


\* SHALL BE CAST IN PRECAST CULVERT HEADWALL.


REINFORCEMENT SHALL BE BUNDLED AND TAGGED AS TO THE LOCATION AS SHOWN ON THIS SHEET.


ALL BENDS IN REINFORCING STEEL TO BE MADE ABOUT A PIN OF THE MINIMUM DIAMETER ALLOWED BY THE STANDARD SPECIFICATIONS.


TOLERANCES IN CUTTING AND BENDING BARS ARE AS ESTABLISHED IN THE MANUAL OF STANDARD PRACTICE OF THE CONCRETE REINFORCING STEEL INSTITUTE AND DETAILING MANUAL OF THE AMERICAN CONCRETE INSTITUTE.

WHERE FIELD CUTTING OF EPOXY BARS IS REQUIRED. THE CONTRACTOR SHALL REPAIR THE EPOXY COATING AT THE CUT END AS PROVIDED FOR IN STANDARD SPECIFICATION 706.03.E.8.









RJD RGW INAL CK'D BY MDW APP'D BY

SNELL ENVIRONMENTAL GROUP. INC. A DLZ Company 151 W. CONGRESS, SUITE 328 DETROIT, MICHIGAN 48226



CITY OF DETROIT MICHIGAN

ITEM NO.

1500000 | MOBILIZATION, MAX.

2040020 STRUCTURES, REMOVE

7060002 | CONCRETE, GRADE T

8130015 | RIPRAP, HEAVY

8160072 MULCH ANCHORING 8160077 MULCH BLANKET

8160007 | SEEDING, MIXTURE TUF

8160003 WATER

7060002 CONCRETE, GRADE D 7060020 SUBSTRUCTURE CONCRETE

7060030 | REINFORCEMENT, STEEL

7110007 | BRIDGE RAILING, ONE TUBE

2050010 EMBANKMENT, CIP

3010002 SUBBASE. CIP

2020002 TREE, REMOVE, 451 TO 900 mm 2040005 CURB, REMOVE

2080025 | EROSION CONTROL, SILT FENCE

4040030 UNDERDRAIN. FOUNDATION. 100 mm

3050001 BITUMINOUS BASE CRUSHING AND SHAPING

7060031 REINFORCEMENT, STEEL, EPOXY COATED

7060250 STRUCTURE NAME PLATE
7110004 BRIDGE RAILING, SOLID PARAPET TYPE

8030002 SIDEWALK, CONCRETE, 100 mm 8120036 BARRICADE, TYPE III, LIGHTE, FURN.

8120037 BARRICADE, TYPE III. LIGHTED. OPER.

8120041 CONCRETE BARRIER, TEMPORARY, FURNISHED 8120042 CONCRETE BARRIER, TEMPORARY, OPERATED

8160020 FERTILIZER. CHEMICAL NUTRIENT. CLASS A

7060040 CONCRETE, LOW TEMPERATURE PROTECTION

4017102 12 802 X 4267 PRECAST CONC HREE-SIDED BOX CULVERT

8120060 SIGN, TYPE B TEMPORARY, PRISMATIC RETRELEC SHEETING

4040110 UNDERDRAIN, OUTLET ENDING, OO mm
6020206 CONCRETE PAVEMENT WITH INTEGRAL CURB (TYPE IIIR), REINFORCED 240 mm
7040003 STEEL SHEET PILING, TEMP., LEFT IN PLACE

2060002 BACKFILL, STRUCTURE, CIP

2060011 EXCAVATION, FOUNDATION

3020010 AGGREGATE BASE, 100 mm

RIVERSIDE AVE. OVER CANAL (BW-242)

STEEL REINFORCEMENT SCALE NOT TO SCALE AND QUANTITIES

SUMMARY OF QUANTITIES

ITEM DESCRIPTION

9641-5160-01 Ra OF 8

METRIC

UNIT QUANTITY

110

400

500 210

42

556

345

13

55

1748

768

117

27

27 33

4

30.5 30.5

<u>66</u> 5

160

Lsum

Lsum

m3

m3

m3

m

m3

m2

m2

m2

m3

kg

ea

m

m2 ea

90

m m

m2

m2

KL

kg

kg

m2

ea m

CURVE AND ALIGNMENT DATA ARE IN NETERS. STATIONS ARE IN KILOMETERS + METERS.

\96415160.01\bridge\final\08bar0 Feb. 2, 1999 16.36:16