



OTHERWISE SHOWN. ELEVATIONS, COORDINATES, STATIONS ARE IN MILLIMETERS UNLESS DIMENSIONS ARE IN KILOMETERS + METERS.

DSON BY	F.T.	7-97
DR.N BY	J.E.	7-97
CK'D BY	GDP	7-97
APP'D BY		



SNYLL ENVIRONMENTAL GROUP, INC. & D.L.C. COMPANY
151 W. FORDHAM ST., SUITE 200
DETROIT, MICHIGAN 48226
TELEPHONE: 313.467.0000



CITY OF DETROIT
MICHIGAN

KORTE AVE. OVER
THE FOX CREEK
TITLE SHEET

SCALE	NOT TO SCALE
PROJECT NO.	9641-5160-02
SHEET NO.	1 OF 9



CITY OF DETROIT
MICHIGAN
DEPARTMENT OF PUBLIC SERVICE
PLAN AND PROFILE OF PROPOSED
BRIDGE REPLACEMENT PROJECT
JOB NO. _____
REPLACEMENT OF THE KORTE AVENUE
BRIDGE OVER FOX CREEK

INDEX OF SHEETS

PLANS	SHEET NO.
1	TITLE SHEET
2	GENERAL PLAN OF SITE
3	LOG OF BORINGS
4	GENERAL PLAN OF STRUCTURE
5	FOOTING PLAN AND DETAILS
6	MISCELLANEOUS DETAILS
7	PRECAST CURB/T SPECIFICATIONS
8	STEEL REINFORCEMENT AND QUANTITIES
9	DETOUR ROUTE DETAILS
R-125A	LIGHTED ARROWS AND BARRICADES
R-96A	SOIL EROSION AND SEDIMENTATION CONTROL MEASURES
B-103B	MOLDING, BEVEL, LIGHT STANDARD ANCHOR BOLT ASSEMBLY AND NAME PLATE DETAILS
B-18B	BRIDGE RAILING, SOLID PARAPET TYPE
B-24A	BRIDGE RAILING, 1 TUBE

THE DESIGN OF THIS STRUCTURE IS BASED ON CURRENT ASHTO STANDARD SPECIFICATIONS FOR HIGHWAY BRIDGES MS18 LOADING. LIVE LOAD PLUS IMPACT DEFLECTION DOES NOT EXCEED 1/1000 OF THE SPAN LENGTH. EXCEPT WHERE OTHERWISE INDICATED ON THESE PLANS, THE PROPOSAL, AND SUPPLEMENTAL SPECIFICATIONS CONTAINED HEREIN, ALL MATERIALS AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE MICHIGAN DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR CONSTRUCTION 1996 EDITION.


THE STATIONING AS SHOWN ON THESE PLANS FOR THE INTERSECTION OF THE CENTERLINE OF BRIDGE AND ROADWAY CENTERLINE IS BELIEVED TO BE CORRECT. IT SHALL, HOWEVER, BE CHECKED AT THE TIME OF STARTING CONSTRUCTION. AND IF THE STATIONING SHOWN ON THE PLANS IS INCORRECT IT SHALL BE REPORTED TO THE DESIGN OFFICE IN DETROIT, AND THE STRUCTURE SHALL BE STAKED OUT USING THE ACTUAL INTERSECTION OF THE CENTERLINE OF THE BRIDGE AND ROADWAY CENTERLINE AS THE CONTROL POINT.

ALL EXPOSED CONCRETE CORNERS SHOWN SQUARE ON THE PLANS SHALL BE BEVELED WITH 13 mm TRIANGULAR MOLDINGS EXCEPT AS OTHERWISE NOTED. THE DESIGN OF THE STRUCTURAL MEMBERS IS BASED ON MATERIAL OF THE FOLLOWING GRADES AND STRESSES.

CONCRETE: GRADE S2
f'c = 21 MPa
CONCRETE: GRADE D
f'c = 28 MPa
STEEL REINFORCEMENT:
fy = 400 MPa

ALL DIMENSIONS ON THESE PLANS ARE IN MILLIMETERS EXCEPT AS NOTED.








UTILITIES

AMERITECH 4000 ALLEN RD. ROOM 101 ALLEN PARK, MICHIGAN 48101 ATTN: DAVE BUCIENSKI PHONE NO.: (313) 389-9819
CITY OF DETROIT WATER & SEWERAGE DEPT 735 RANDOLPH ST. DETROIT, MICHIGAN 48226 PHONE NO.: (313) 224-4800
DETROIT EDISON 2000 SECOND AVE. ROOM 607 G.O. DETROIT, MICHIGAN 48226 PHONE NO.: (313) 235-6597
MICHIGAN CONSOLIDATED GAS CO. DRAWING CLERK NOBLE SECOND FLOOR 3200 HOBSON DETROIT, MICHIGAN 48201 PHONE NO.: (313) 571-7236

DRIVEWAYS TO BE PAVED TO PROVIDE A
 SMOOTH TRANSITION BETWEEN PROPOSED
 PAVEMENT AND EXISTING DRIVEWAY AS
 DIRECTED BY ENGINEER.



NOTES:
 * THE CONTRACTOR SHALL LOCATE ALL ACTIVE UNDERGROUND UTILITIES THAT THOSE UTILITIES NOT REQUIRING RELOCATION WILL NOT BE DISTURBED.
 * KORTE AVE. TRAFFIC IS TO BE DETOURED OVER THE EXISTING ROADS.
 * DATUM REFERS TO N.A.V.D. DATUM.
 * WATER LEVEL IS SUBJECT TO CHANGE. THE CONTRACTOR IS RESPONSIBLE FOR MAKING HIS OWN DETERMINATION OF WATER LEVELS THAT WILL EXIST DURING CONSTRUCTION.
 * MEASURES SHALL BE TAKEN TO PREVENT DEBRIS FROM FALLING FROM THE STRUCTURE. IF DEBRIS FALLS INTO THE WATERWAY, IT SHALL BE REMOVED WITHIN 24 HOURS, SINCE DISTURBANCE OF THE WATERWAY BOTTOM MAY BE AS HARMFUL AS THE DEBRIS ITSELF. THE PREVENTIVE MEASURES MUST BE MADE AS EFFECTIVE AS POSSIBLE.
 * TEMPORARILY STORED EXCAVATED MATERIAL SHALL NOT BE ALLOWED TO ERODE INTO THE WATERCOURSE.
 * ALL DISTURBED EXISTING GROUND AND ANY NEW FILL SLOPES SHALL BE SEED, FERTILIZED, AND MULCHED AS DIRECTED BY THE ENGINEER. TO BE INCLUDED IN THE PAY ITEMS "SEEDING, MIXTURE TUR, " FERTILIZER, CHEMICAL NUTRIENT, CLASS A," AND "MULCH BLANKET."
 * DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE SHOWN. ELEVATIONS, COORDINATES, CURVE AND ALIGNMENT DATA ARE IN METERS. STATIONS ARE IN KILOMETERS + METERS.



WITNESSES

WITNESS TO CONTROL POINT 102: STA. 9+900 (MAG. NAITL)
N 80° W SE CORNER HOUSE 18.92 m
S 60° E POWER POLE 15.99 m
WITNESS TO CONTROL POINT 103: STA. 10+040 (MAG. NAITL)
N 85° W 762 mm ELM 13.36 m
S 10° E POWER POLE 6.25 m
N 30° W SW CORNER HOUSE 12.10 m

DRN BY	J.E.	7-97
CK'D BY	CDP	7-97
APP'D BY		
DSGN BY	F.T.	7-97

SNELL ENVIRONMENTAL GROUP, INC.
 151 W. CONGRESS SUITE 508
 DETROIT, MICHIGAN 48226
 TELEPHONE (313) 961-4040




FEMI TABABI & ASSOCIATES INC.
 165 CONSUMERS SUITE 1005
 DETROIT, MICHIGAN 48226
 TELEPHONE (313) 961-4040

CITY OF DETROIT
 MICHIGAN

KORTE AVE. OVER THE FOX CREEK BORINGS

LOG OF BORINGS

PROJECT NO. 9641-5160-02
 SHEET NO. 3 OF 9
 SCALE NOT TO SCALE



NOTES:

NUMBERS IN CIRCLES DENOTE NUMBER OF BLOWS REQUIRED TO DRIVE A 50.8 mm SPLIT SPOON SAMPLER 3 SUCCESSIVE 0.15 m INCREMENTS USING A 63.5 kg HAMMER FALLING 0.76 m. WHERE THE SAMPLER IS DRIVEN DISTANCES OTHER THAN THE 0.15 m INCREMENT, THE DISTANCE IS SHOWN IN PARENTHESES TO THE RIGHT OF THE NUMBER OF BLOWS.

NUMBER OF BLOWS PER 0.15 m (X)
 NUMBER OF BLOWS PER 0.15 m (X)
 NUMBER OF BLOWS PER 0.15 m (X)
 NUMBER OF BLOWS PER 0.15 m (X)
 NUMBER OF BLOWS PER 0.15 m (X)
 NUMBER OF BLOWS PER 0.15 m (X)
 NUMBER OF BLOWS PER DISTANCE (mm) XX(XX)
 NUMBER OF BLOWS PER DISTANCE (mm) XX(XX)

CONSISTENCY WAS DETERMINED BY INSPECTION OF SAMPLES AND SUBSTANTIATED BY SOILS RESISTANCE TO DRILLING TOOLS.
 WATER LEVELS MAY BE INFLUENCED BY RESIDUAL BORING WATER.
 THE SOIL BORING LOGS REPRESENT POINT INFORMATION.
 PRESENTATION OF THIS INFORMATION IN NO WAY IMPLIES THAT THAN THE EXACT LOCATION OF THE BORING.
 SOIL BORINGS WERE PERFORMED ON DATES SHOWN BELOW BORING.
 BY: PROFESSIONAL SERVICES INDUSTRIES, INC.
 24355 Capitol Ave.
 Detroit, Mich. 48239
 Phone: (313) 255-4200

METRIC

DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE SHOWN. ELEVATIONS, COORDINATES, CURVE AND ALIGNMENT DATA ARE IN METERS. STATIONS ARE IN KILOMETERS + METERS.

REVISIONS

DRN BY	J.E.	7-97
CHK'D BY	C.D.P.	7-97
APP'D BY		

SNELL ENVIRONMENTAL GROUP, INC. A DLZ Company
 151 W. CONGRESS, SUITE 328
 DETROIT, MICHIGAN 48226
 TELEPHONE 1213 961-4040
 65 GERRARD, SUITE 100, DETROIT, MICHIGAN 48202



PERMI TALABI & ASSOCIATES INC.
 55 GERRARD, SUITE 100, DETROIT, MICHIGAN 48202
 313 961-4040







CITY OF DETROIT

KORTE AVE. OVER THE FOX CREEK

GENERAL PLAN OF STRUCTURE


PROJECT NO. 9641-5160-02
 SHEET NO. 4 OF 9
 SCALE NOT TO SCALE

STATIONS ARE IN METERS UNLESS OTHERWISE SHOWN. ELEVATIONS, COORDINATES, CURVE AND ALIGNMENT DATA ARE IN METERS. DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE SHOWN.



NOTES:
 THE DESIGN OF THIS STRUCTURE IS BASED ON CURRENT AASHTO STANDARD SPECIFICATIONS FOR HIGHWAY BRIDGES MS18 LOADING, LIVE LOAD PLUS IMPACT DEFLECTION DOES NOT EXCEED 1/1000 OF SPAN LENGTH. THE TOP OF THE ROADWAY AND TOPS OF SIDEWALKS ARE PARALLEL TO THE VERTICAL CURVE.
 STEEL SHEET PILING, TEMP. LEFT IN PLACE SHALL BE CUT OFF AS DIRECTED BY THE ENGINEER.
 ALL DEMATERING OPERATIONS, MATERIAL AND LABOR SHALL BE INCLUDED IN THE PAY ITEM "STEEL SHEET PILING, TEMP. LEFT IN PLACE".
 THE DESIGN OF THIS STRUCTURE IS BASED ON CURRENT AASHTO STANDARD SPECIFICATIONS FOR HIGHWAY BRIDGES MS18 LOADING, LIVE LOAD PLUS IMPACT DEFLECTION DOES NOT EXCEED 1/1000 OF SPAN LENGTH.
 THE TOP OF THE ROADWAY AND TOPS OF SIDEWALKS ARE PARALLEL TO THE VERTICAL CURVE.
 STEEL SHEET PILING, TEMP. LEFT IN PLACE SHALL BE CUT OFF AS DIRECTED BY THE ENGINEER.
 ALL DEMATERING OPERATIONS, MATERIAL AND LABOR SHALL BE INCLUDED IN THE PAY ITEM "STEEL SHEET PILING, TEMP. LEFT IN PLACE".

DR. N. BY	J. E.	7-97
APP'D. BY	C. D. P.	7-97
DATE		



SNELL ENVIRONMENTAL GROUP, INC. • A D.L.Z. COMPANY
 151 W. CONGRESS, SUITE 328
 DETROIT, MICHIGAN 48226
 TELEPHONE (313) 961-4040

FPM TALABI & ASSOCIATES INC.
 606 GREENWOOD ST. 8TH. DETROIT, MICHIGAN, 48226
 Making it better for you

CITY OF DETROIT
 MICHIGAN
 KORTE AVE.
 OVER THE FOX CREEK

SCALE NOT TO SCALE
 PROJECT 9641-5160-02
 SHEET NO. 5 OF 9






STATIONS ARE IN MILLIMETERS UNLESS OTHERWISE SHOWN. ELEVATIONS, COORDINATES, CURVE AND ALIGNMENT DATA ARE IN METERS. STATIONS ARE IN KILOMETERS + METERS.

METRIC

POUR	AMOUNT
A	59.4 m ³
B	29.9 m ³
TOTALS	89.0 m³


SUBSTRUCTURE CONCRETE QUANTITIES

NOTES:
 FOR ABUTMENT A AND B THE MAXIMUM FOUNDATION PRESSURE IS CALCULATED TO BE 278 KPA AVERAGE DEAD LOAD PLUS LIVE LOAD PRESSURE.



FILE NAME: 06ADRF10.DGN

DRN BY	H.J.	6-97
DRN BY	J.E.	6-97
CK'D BY	C.D.P.	7-97
APP'D BY		



SNELL ENVIRONMENTAL GROUP, INC. • a DLZ Company
 151 W. CONGRESS, SUITE 328
 DETROIT, MICHIGAN 48226
 TELEPHONE: (313) 961-4040

FEMI TALABI & ASSOCIATES INC.
 615 GERRARD SUITE 1505 DETROIT, MICHIGAN 48226
 Making it better for you
 DETROIT

CITY OF DETROIT
 MICHIGAN

KORTE AVE.
 OVER THE
 FOX CREEK




MISCELLANEOUS
 DETAILS

PROJECT NO. 9641-5160-02
 SHEET NO. 6 OF 9
 SCALE NOT TO SCALE


DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE SHOWN. ELEVATIONS, COORDINATES, CURVE AND ALIGNMENT DATA ARE IN METERS. STATIONS ARE IN KILOMETERS + METERS.

METRIC


TYPICAL PLAN OF SIDEWALK



TYPICAL SECTION THRU PRECAST WINGWALL



WINGWALL ELEVATION




SPECIFICATIONS FOR MANUFACTURE AND INSTALLATION OF PRECAST CULVERT BRIDGE SYSTEMS

REV'S	DESCRIPTION	6. DESIGN	8. TESTING AND INSPECTION	13. REJECTION	14. MARKING	15. CONSTRUCTION REQUIREMENTS	16. MEASUREMENT AND PAYMENT	9. JOINTS	10. WORKMANSHIP AND FINISH	11. REPAIRS	12. INSPECTION	7. PERMISSIBLE VARIATIONS	5. MANUFACTURE	4. MATERIALS - STEEL REINFORCEMENT AND HARDWARE	3. MATERIALS - CONCRETE	2. TYPES	1. DESCRIPTION
1	This work shall consist of constructing a Con/Spun culvert or approximately close conformity with the lines, grades, design and approved by the manufacturer with this specification shall be designated by span and reinforcement details shall be as prescribed in the plan and the shop drawings provided by the manufacturer subject to the provisions of Section 7. The minimum concrete compressive strength shall be 400 MPa.	6.1	8.1	13.1	14.1	15.1	16.1	9.1	10.1	11.1	12.1	7.1	5.1	4.1	3.1	2.1	1.1
2	Precast reinforced concrete Con/Spun culverts or approved equipment in accordance with this specification shall be designated by span and reinforcement details shall be as prescribed in the plan and the shop drawings provided by the manufacturer subject to the provisions of Section 7. The minimum concrete compressive strength shall be 400 MPa.	6.2	8.2	13.2	14.2	15.2	16.2	9.2	10.2	11.2	12.2	7.2	5.2	4.2	3.2	2.2	1.2
3	The concrete for the culverts shall be air-entrained when placed in areas subject to freeze-thaw conditions, composed of portland cement, fine and coarse aggregates, admixtures and water. Concrete shall contain a minimum of 2 percent air.	6.3	8.3	13.3	14.3	15.3	16.3	9.3	10.3	11.3	12.3	7.3	5.3	4.3	3.3	2.3	1.3
4	Water Reducing Admixture - The manufacturer may submit for approval by the Engineer, water-reducing admixture for the purpose of increasing workability and reducing the water requirement for the concrete.	6.4	8.4	13.4	14.4	15.4	16.4	9.4	10.4	11.4	12.4	7.4	5.4	4.4	3.4	2.4	1.4
5	Mixture - The aggregates, cement and water shall be proportioned and mixed in a batch mixer to produce a homogeneous concrete meeting the strength requirements of this specification. The proportion of portland cement in the mixture shall not be less than 256 kg (5 sacks) per cubic meter of concrete.	6.5	8.5	13.5	14.5	15.5	16.5	9.5	10.5	11.5	12.5	7.5	5.5	4.5	3.5	2.5	1.5
6	Internal Dimensions - The internal dimension shall vary slightly, but not more than 1% from the design dimensions nor more than 40 mm, whichever is less. The punch dimensions shall vary not more than 20 mm from the design dimension.	6.6	8.6	13.6	14.6	15.6	16.6	9.6	10.6	11.6	12.6	7.6	5.6	4.6	3.6	2.6	1.6
7	Water Curing - The culverts may be water cured by any method that will keep the sections moist. Membrane Curing - A sealing membrane conforming to the requirements ASTM Specification C 309 may be applied and shall be left intact until the required concrete temperature at the time of application shall be within + 6 degree C of the atmospheric temperature. All surfaces shall be kept moist prior to the application of the compounds and shall be damp when the compound is applied.	6.7	8.7	13.7	14.7	15.7	16.7	9.7	10.7	11.7	12.7	7.7	5.7	4.7	3.7	2.7	1.7
8	Forms - The forms used in manufacture shall be sufficiently rigid and accurate to maintain the culvert dimensions within the permissible variations given in Section 7. All casting surfaces shall be of smooth material.	6.8	8.8	13.8	14.8	15.8	16.8	9.8	10.8	11.8	12.8	7.8	5.8	4.8	3.8	2.8	1.8
9	Handling - Handling devices or hoists shall be permitted in no case shall the cover over the reinforcement be less than 40 mm for the outside circumference (steel reinforcement) for the inside circumference. The rebar shall be measured to the external or internal surface of the culvert. These tolerances or cover requirements shall be measured to the external or internal surface of the culvert.	6.9	8.9	13.9	14.9	15.9	16.9	9.9	10.9	11.9	12.9	7.9	5.9	4.9	3.9	2.9	1.9
10	Storage - The culverts shall be stored in such a manner to prevent cracking or damage. The units shall be stored in an upright position until the compressive strength is a minimum of 28 MPa.	6.10	8.10	13.10	14.10	15.10	16.10	9.10	10.10	11.10	12.10	7.10	5.10	4.10	3.10	2.10	1.10
11	Area of Reinforcement - The gross of steel reinforcement shall be designed as shown in the manufacturer's shop drawings. Steel areas greater than those required shall not be cause for rejection. The permissible variation in diameter of any reinforcement shall conform to the tolerances specified in the drawings.	6.11	8.11	13.11	14.11	15.11	16.11	9.11	10.11	11.11	12.11	7.11	5.11	4.11	3.11	2.11	1.11
12	Dimensions are in millimeters unless otherwise shown. ELEVATIONS, COORDINATES, CURVE AND ALIGNMENT DATA ARE IN METERS. STATIONS ARE IN KILOMETERS + METERS.	6.12	8.12	13.12	14.12	15.12	16.12	9.12	10.12	11.12	12.12	7.12	5.12	4.12	3.12	2.12	1.12
13	SCALE NOT TO SCALE	6.13	8.13	13.13	14.13	15.13	16.13	9.13	10.13	11.13	12.13	7.13	5.13	4.13	3.13	2.13	1.13
14	PROJECT NO. 9641-5160-02	6.14	8.14	13.14	14.14	15.14	16.14	9.14	10.14	11.14	12.14	7.14	5.14	4.14	3.14	2.14	1.14
15	SHEET NO. 7 OF 9	6.15	8.15	13.15	14.15	15.15	16.15	9.15	10.15	11.15	12.15	7.15	5.15	4.15	3.15	2.15	1.15

FILE NAME: 070707.DWG

App. D. BY	
DR. N. BY	J.E.
CK. D. BY	C.D.P.
DSGN. BY	F.T.
	7-97
	7-97
	7-97



SNELL ENVIRONMENTAL GROUP, INC.
 191 W. CONGRESS, SUITE 326
 DETROIT, MICHIGAN 48226
 TELEPHONE: (313) 961-4040

FEMI TALABI & ASSOCIATES INC.
 615 GERRARD, SUITE 1005, DETROIT, MICHIGAN, 48226



CITY OF DETROIT

KORTE AVE. OVER THE FOX CREEK

STEEL REINFORCEMENT AND QUANTITIES


NO. SHEET 8 OF 9
 PROJECT NO. 9641-5160-02
 SCALE NOT TO SCALE

DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE SHOWN. ELEVATIONS, COORDINATES, CURVE AND ALIGNMENT DATA ARE IN METERS. STATIONS ARE IN KILOMETERS + METERS.

METRIC

REINFORCEMENT SHALL BE BUNDLED AND TAGGED AS TO THE LOCATION AS SHOWN ON THIS SHEET.
 ALL BENDS IN REINFORCING STEEL TO BE MADE ABOUT A PIN OF THE MINIMUM DIAMETER ALLOWED BY THE STANDARD SPECIFICATIONS.
 TORQUES IN CUTTING AND BENDING BARS ARE AS ESTABLISHED IN THE MANUAL OF STANDARD PRACTICE OF THE CONCRETE REINFORCING STEEL INSTITUTE AND DETAILING MANUAL OF THE AMERICAN CONCRETE INSTITUTE.
 WHERE FIELD CUTTING OF EPOXY BARS IS REQUIRED, THE CONTRACTOR SHALL REPAIR THE EPOXY COATING AT THE CUT END AS PROVIDED FOR IN STANDARD SPECIFICATION 706.03.E.8.

ITEM NO.	ITEM DESCRIPTION	UNIT	QUANTITY
1500000	MOBILIZATION, MAX.	L-sum	1
2040005	CURB, REMOVE	m	50
2040013	SIDEWALK, REMOVE	m ²	80
2040200	STRUCTURES, REMOVE	L-sum	1
2047102	FENCE, REMOVAL, SALVAGE AND REPLACE	m	20
2050010	EMBANKMENT, CIP	m ³	100
2060002	BACKFILL, STRUCTURE, CIP	m ³	1200
2060011	EXCAVATION, FOUNDATION	m ³	500
2080025	EROSION CONTROL, SILT FENCE	m	40
3020014	AGGREGATE BASE, 140 mm	m ²	92
3027000	AGGREGATE, 6A (L.M)	m ³	42
3050001	BITUMINOUS BASE CRUSHING AND SHAPING	m ²	157
4017102	10 973 X 3962 PRECAST CONC THREE-SIDED BOX CULVERT	m	12.8
5020057	BIT MIXTURE 3C	+	30
5020059	BIT MIXTURE 4C	+	28
7040003	STEEL SHEET PILING, TEMP. LEFT IN PLACE	m ²	514
7060007	CONCRETE, GRADE D	m ³	13
7060010	CONCRETE, GRADE S2, SUBFOOTING	m ³	4
7060020	SUBSTRUCTURE CONCRETE	m ³	89
7060030	REINFORCEMENT, STEEL	kg	1939
7060031	REINFORCEMENT, STEEL, EPOXY COATED	kg	779
7060250	STRUCTURE NAME PLATE	eo	2
7100001	JOINT WATERPROOFING	m ²	7
7100004	BRIDGE RAILING, SOLID PARAPET TYPE	m	24
7110007	BRIDGE RAILING, ONE TUBE	m	24
8027102	MISC. CURB, CONCRETE, DETAIL CD	m	24
8030002	SIDEWALK, CONCRETE, 100 mm	m	56
810241	PAVT MKKG, REGULAR DRY, 100 mm, WHITE	m ²	92
810242	PAVT MKKG, REGULAR DRY, 100 mm, YELLOW	m	80
8120026	PLASTIC DRUM, LIGHTED, FURN	eo	20
8120027	PLASTIC DRUM, LIGHTED, OPER.	eo	20
8120036	BARICADE, TYPE III, LIGHTED, FURN.	eo	8
8120037	BARICADE, TYPE III, LIGHTED, OPER.	eo	8
8120060	SIGN, TYPE B TEMPORARY, PRISMATIC RETRFLC SHEETING	m ²	32
8160007	SEEDING, MIXTURE TUR	kg	2
8160020	FERTILIZER, CHEMICAL NUTRIENT, CLASS A	kg	2
8160077	MULCH BLANKET	m ²	70



* SHALL BE CAST INTO PRECAST HEADWALL.

BAR	DIMENSIONS											NO. TOTAL	RETD. MASS	
	a	b	c	d	e	f	g	h	j	k	m			
A1905533	5533												28	346
A1913000	13000												10	291
A1913558	13358												14	418
C1903302	866	2302	0	0	0	0	0	0	0	0	0	0	10	75
C1903557	906	2557	0	0	0	0	0	0	0	0	0	0	10	79
D1302968	1059	850	1059										84	248
D1304334	1742	850	1742										112	482
E01901878	870	138	870										56	235
EA131546	11546												32	367
EA1301650	1650												108	177
SUBTOTAL = 1939 kg														
EPOXY SUBTOTAL = 779 kg														

SIGN CHART				
I.D. NUMBER	SIGN	DESIGNATION	SIZE	NUMBER REQUIRED
1		W20-3	1200X1200	1
2		W20-2	1200X1200	5
3		W20-3	1200X1200	1
4		D3-1	900X300	1
5		M6-1B	525X375	1
6		R11-4	1500X750	1
7		R11-2	1200X750	1
8		D3-1	900X300	4
9		M4-9	900X300	7
10		D3-1	900X300	2
11		M4-8A	600X450	2
12		R11-2	1200X750	1
13		W20-3	1200X1200	4

DR. N. BY	J.E.	7-97
CK. D. BY	C.D.P.	7-97
APP. D. BY		

SNELL ENVIRONMENTAL GROUP, INC. A DLZ COMPANY
 151 W. CONGRESS, SUITE 328
 DETROIT, MICHIGAN 48226
 TELEPHONE (313) 961-4040

FEMI TALABI & ASSOCIATES INC.
 616 CHURCH, SUITE 1605, DETROIT, MICHIGAN 48226



CITY OF DETROIT
 MICHIGAN

KORTE AVE. OVER

DETOUR ROUTE
 DETAILS

NO. SHEET	9 OF 9
PROJECT NO.	9641-5160-02
SCALE	NOT TO SCALE

DETOUR PLAN KORTE AVE.



NOTES:
 THE CONTRACTOR WILL FURNISH AND ERECT THE SIGNS LISTED ON THE SIGN CHART AT THE LOCATIONS SHOWN.
 AS DIRECTED BY THE ENGINEER, THE CONTRACTOR SHALL PROVIDE AND MAINTAIN ANY ADDITIONAL SIGNS, BARRICADES AND LIGHTS WITHIN THE PROJECT TO PROTECT THE TRAFFIC AND WORK AREA.
 THE CONTRACTOR SHALL PLACE SANDBAGS ON BARRICADES TO PREVENT MOVEMENT OF THE BARRICADES. THE CONTRACTOR SHALL ATTACH AND MAINTAIN THREE (3) STEADY BURN AMBER LIGHTS (TYPE "C") ON EACH OF THE BARRICADES.
 THE CONTRACTOR SHALL ATTACH AND MAINTAIN ONE (1) BATTERY OPERATED AMBER FLASHER LIGHTS (TYPE "A") AND ONE (1) ORANGE FLUORESCENT DAY-GLO FLAG ON EACH ADVANCE CONSTRUCTION SIGN (SIGNS 1, 2 & 3).
 TRAFFIC CONTROL SIGNS WHICH ARE REMOVED FROM THE VICINITY OF THE PROJECT DUE TO INTERFERENCE SHALL BE TURNED OVER TO THE CITY, UPON COMPLETION OF THE PROJECT. TRAFFIC CONTROL SIGNS AND STREET NAME SIGNS WILL BE RESET IN THEIR PROPER POSITION BY THE CONTRACTOR.
 THE CONTRACTOR SHALL NOT BEGIN ANY OPERATIONS ON THE PROJECT UNTIL ALL OF THE SIGNS HAVE BEEN POSITIONED AND FLASHER LIGHTS AND FLAGS ARE ATTACHED TO ALL REQUIRED SIGNS AND BARRICADES.
 ANY OTHER SIGNS WHICH THE CONTRACTOR MAY BE REQUIRED TO FURNISH SHALL CONFORM TO THE MICHIGAN MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES.
 ALL CONSTRUCTION SIGNS SHALL CONFORM TO MDOT 1996 STANDARD SPECIFICATIONS FOR CONSTRUCTION 812.02-B.1.
METRIC
 DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE SHOWN. ELEVATIONS, COORDINATES, CURVE AND ALIGNMENT DATA ARE IN METERS.
 STATIONS ARE IN KILOMETERS + METERS.

SIGN TYPE LEGEND

	TYPE III BARRICADE
	SIGN, TYPE B

MISCELLANEOUS QUANTITIES

ITEM	UNIT	AMOUNT
BARRICADE, TYPE III, LIGHTED, OPER	ea	8
BARRICADE, TYPE III, LIGHTED, FURN	ea	8
PLASTIC DRUM, LIGHTED, OPER	ea	20
PLASTIC DRUM, LIGHTED, FURN	ea	20
PLASTIC DRUM, LIGHTED, OPER	ea	20
SIGN, TYPE B, TEMPORARY, PRISMATIC RETROREFLECTIVE SHEETING	sq. ft.	32