
ELEV



COFFERDAM LEFT - IN PLACE (TYP.)

CURB & GUTTER (TYP.) - SEE SH # FOR DETAILS

Ç ROADWAY & ∽ CONSTRUCTION Ç

MISCELLANEOUS QUANTITIES					
LS   LS   LS   LS   LS   LS   LS   LS	Monitoring Vibrations (Structures) Monitoring Vibrations (Sanitary Sewers) Structures, Rem (B01 of 63021) Masonry and Conc. Structures, Rem. Structures, Rem Portions (B01 of 63021) False Decking Excavation, Edn Backfill, Structure, CIP Embankment, CIP Excavation, Earth Non Haz Containminated Material Handling and Disposal, LM Riprap, Heavy, Special Articulating Concrete Block System, 6 Inches Conferdams, Left in Place (C01 of 63821) Conc. Surface Coating Conc. Quality Assurance, Structure Patching Mortar or Conc. ** Patch Formine **				

\* TO BE USED AS DIRECTED BY THE ENGINEER FOR REPAIRS ON THE EXISTING RETAINING WALL.

## **EROSION AND SEDIMENTATION CONTROL OUANTITY** KEY PAY ITEM (55) Erosion Control, Filter Bag Turbidity Curtain (Shallow) Erosion Control, Silt Fence Erosion Control, Inlet Protection, Fabric Drop Sedimentation Control

SUMMARY OF HYDRAULIC ANALYSIS									
EXISTING				PROPOSED					
FLOOD DATA	DISCHARGE (CFS)	WATER SURFACE ELEV. AT U/S FACE OF STRUCTURE	VELOCITY AT D/S FACE (FPS)	WATER SURFACE ELEV. AT U/S FACE OF STRUCTURE	VELOCITY AT D/S FACE (FPS)	WATERWAY AREA (SFT) AT D/S FACE	CHANGE IN WS EL 3 U/S OF PROPOSED STRUCTURE		
50 YEAR									
100 YEAR									
MAXIMUM BRIDGE AREA BELOW LOW CHORD ISSQUARE FEET									

THE WATER SURFACE AND/OR ENENGY GRADE ELEVATIONS SHOWN ON THE ABOVE HYDRAULIC TABLE ARE TO BE USED FOR COMPARISON PURPOSES ONLY AND ARE NOT TO BE USED FOR ESTABLISHING A REGULATORY FLOORPLAIN. THE ELEVATIONS MAY NOT BE USED PROVIDED THEY ARE VERIFIED WITH THE LAND AND WATER MANAGEMENT DIVISION, MICHIGAN DEPARTMENT OF ENVIRONMENTAL QUALITY.

## **NOTES:**

THE DESIGN OF THIS STRUCTURE IS BASED ON CURRENT AASHTO STANDARDS SPECIFICATIONS FOR HIGHWAY BRIDGES HS25 LOADING. THE LOAD FACTOR METHOD OF DESIGN WAS USED FOR THIS STRUCTURE.

THE REMOVAL OF THE EXISTING STRUCTURE, SLOPEWALLS AND GABIONS IS INCLUDED IN THE PAY ITEM, "Structures, Rem B01 of 63021)". SEE 'STRUCTURES REMOVAL SEQUENCE' ON SHEET \_\_\_\_

REMOVAL OF THE EXISTING SUBSTRUCTURE UNITS SHALL BE ISOLATED FROM THE WATERWAY USING TEMPORARY STEEL SHEET PILING. TEMPORARY SHEETING FOR THE REMOVAL SHALL ADHERE TO THE SAME REQUIREMENTS FOR CONSTRUCTION AND DE-WATERING AS THE COFFERDAM. TEMPORARY SHEETING, SHALL BE CUT OFF 1'-0" BELOW FINISH GRADE AND SHALL NOT INTERFERE WITH PROPOSED CONSTRUCTION. ALL COST ASSOCIATED WITH THE TEMPORARY SHEETING IS INCLUDING IN THE REMOVAL ITEMS.

THE TOP 2' (±) OF THE EXISTING RETAINING WALL SHALL BE REMOVED BY SAW CUTTING. WORK IS INCLUDED IN "Structures, Rem Portions (B01 of 63021)". SEE 'RETAINING WALL REMOVAL AND CONSTRUCTION SEQUENCE" ON SHEET

REMOVAL OF EXISTING SHEETING IN THE SLOPE ADJACENT TO THE PROPOSED RETAINING WALL IS INCLUDED IN ™Structures, Rem Portions (B01 of 63021)¹.

DURING WORK ON THE EXISTING AND PROPOSED RETAINING WALLS CASE SHALL BE TAKEN TO PREVENT ANY MATERIAL FROM ENTERING THE WATERWAY. THE CONTRACTOR SHALL PROPOSED A SYSTEM FOR PROTECTION OF THE WATERWAY & SUBMIT IT TO THE ENGINEER FOR APPROVAL. PAID FOR AS 'Sedimentation Control . SEE SPECIAL PROVISION.

PAYMENT FOR FALSE DECKING SHALL BE BASED ON THE AREA OF THE EXISTING ARCH BARREL OVER THE WATERWAY REGARDLESS OF THE SIZE OF THE BARGE OR PLATFORM USED. THE CONTRACTOR SHALL TAKE CARE NOT TO ALLOW THE EXISTING EARTH FILL TO FALL INTO THE WATERWAY.

GEOTEXTILE LINER SHALL BE PLACED ON ALL SLOPES PRIOR TO PLACING RIPRAP. PAYMENT FOR GEOTEXTILE LINER SHALL BE INCLUDED IN THE PAYMENT FOR "Riprap, Heavy, Special".

WITHOUT THE PREVENTIVE MEASURES SHOWN ON THESE PLANS, THERE IS A POSSIBILITY THAT STREAM BED SCOUR MAY OCCUR. THE ESTIMATED TOTAL SCOUR DEPTH IS CACULATED TO BE 6.6.° AT ABUMENT A AND 13.6° AT ABUMENT B. THESE DEPTHS ARE BASED ON A 100 YEAR RUNOFF EVENT.

THE DRAINAGE AREA CONTRIBUTORY TO THIS CROSSING IS 18 SQUARE MILES.

BROKEN CONCRETE SHALL NOT BE USED AS RIPRAP.

THE TREMIE SEAL DESIGN WAS BASED ON A WATER SURFACE AT EL.

THE WIDTH OF THE TREMIE UNDER THE STRUCTURE MAY NOT BE INCREASED EXCEPT IN THE SOUTHWEST QUADRANT IN THE VICINITY OF THE EXISTING AND PROPOSED SANITARY SEWER.

THE USE OF VIBRATORY HAMMERS FOR INSTALLATION COFFERDAM SHALL NOT BE ALLOWED.

DEWATERING OF THE COFFERDAM IS TO BE MADE THRU FILTER BAGS UNTIL COMPLETION OF THE TREMIE SEAL. ALL COST ASSOCIATED WITH DEWATERING ARE THE REPONSIBILITY OF THE CONTRACTOR.

COFFERDAMS IN STREAM SHALL BE CUT OFF AT ELEVATION OR A MINIMUM OF 1'-0' BELOW THE STREAM BOTTOM OR 1'-0" BELOW GRĀDE. WORK IS INCLUDED IN THE BID ITEM, "Cofferdams, Left in Place (C01 of 63821").

CONCRETE SURFACE COATING IS TO BE APPLIED TO BOTH SIDES OF THE RAILING. THE HEADRAIL FACIA, THE CULVERT AND PEDESTAL WALL END FACES, THE TOP AND EXPOSED SIDE OF THE WINCWALL, RETURNWALLS AND THE RETAINING WALL. COATING SHALL EXTEND 6 INCHES MINIMUM BELOW FINISHED GRADE. THE ESTIMATED AREA OF COATING IS 1500 SQUARE YARDS.

ALL EXCAVATION ON THE PROJECT SHALL BE CONSIDERED NONHAZARDOUS CONTAMINATED. STORAGE AREA FOR THE MATERIAL ON SITE MAY BE LIMITED.

CHECKED BY

PLAN

CITY OF DETROIT CITY ENGINEERING DIVISION - D.P.W. BUREAUS OF STREETS AND HIGHWAYS

WEST PARKWAY CULVERT OVER ROUGE RIVER

CONTRACT ASSIGNMENT NO.

ESTIMATE REVISIONS

REF P + B / STA. EL. XXX

GRASS

SIDEWALK

GENERAL PLAN OF STRUCTURE