



REMOVAL QUANTITIES

6 EA	TREE, REM, 6 INCH TO 18 INCH
3 EA	TREË, REM, 18 INCH TO 36 INC
4 EA	DR STRUCTURE, REM
436 FT	CURB AND GUTTER, REM
436 FT	GUARDRAIL, REM
970 SYD	PAVT, REM
291 SVD	SIDEWALK REM

NOTES:

NOTE 1: SEE CULVERT PLANS FOR REMOVAL OF EX. CULVERT.

NOTE 2: EX. POWER AND LIGHT POLES ON SIDE WILL BE PERMANENTLY REMOVED FOR CONSTRUCTION OF THIS PROJECT (BY DTE)

NOTE 3: EX. WATER MAIN BECOMES LIVE AGAIN BETWEEN NOT BLOCK OUT ANY EXISTING LIVE FEEDS.

NOTE 4:
EX. GAS WILL BE SHUTDOWN BY MICHCON (DTE) PRIOR TO CONSTRUCTION.
CONTRACTOR SHALL REMOVE THE OUT OF SERVICE SECTION DURING SIDEWALK
REMOVAL MICHCON (DTE) MAY REPLACE ____ DURING CONSTRUCTION.

NOTE 5:
POSSIBLE WEIR REMOVAL WITHIN SEWER. REMOVED AS DIRECTED
BY THE ENCINEER. WORK SHALL BE PAID FOR AS MASONRY
CONC STRUCTURE, REM.

NOTE 6: VERIFY REMOVAL OF EXISTING SANITARY SEWER WITH THE DWSD ENGINEER.

						BY	CHECKED BY	APPROVED:	
					PLAN				
					FLAN				
								CNGMCC# 0/ 514CC15	1
					GRADE				
					ESTIMATE				-
DESCRIPTION	DR I	ско	APV	DATE		****	*****		
REVISIONS					FINAL]

CITY OF DETROIT CITY ENGINEERING DIVISION - D.P.W. BUREAUS OF STREETS AND HIGHWAYS FOR

WEST PARKWAY CULVERT OVER ASHCROFT - SHERWOOD DRAIN

SHEET 4 OF 39 SHEETS

REMOVAL

ASSIGNMENT NO.