SEWER O.K. J. Liepah 5/11/56

REVISIONS OLD MAP 10-19-35

AT ⑦ ADDED SEWER, STUB IN GROVE, PROF. ON FENTON FR. GROVE TO MCMICHAEL'S RD. DWG. 9 SEWER LINE FR. STUB TO LATERAL SEWER.
LATERAL SEWER COMPLETED 11-24-54 W.O.

SUPPLEMENTARY DETAILS

C-324A	C-390	C-587	C-739B
C-325	C-524	C-733	C-938
C-326A	C-585	C-739	C-1608
C-327	C-586	C-739A	C-1783

NOTE!
BEFORE STARTING CONSTRUCTION CONTRACTOR MUST CHECK WITH UTILITIES FOR LOCATIONS OF EXISTING STRUCTURES WHETHER OR NOT INDICATED ON PLANS.

PLAN SCALE DISTORTED
LOTS & ALLEYS 1"=100'
STREET WIDTHS 1"=50'

By D.P.W.
DRAINAGE COMPLETED 10-27-54
PAVING COMPLETED
From Puritan to Florence Only in This Contract P.W. 2767 W C.C. 2-19-57

QUANTITIES	ESTIMATED LOTS	ESTIMATED CITY	FINAL LOTS	FINAL CITY
EXCAVATION CU.YDS.	525	167		
NEW CURB II LIN.FT.		16		
8:6:8 PAVING SQ.YDS.	2653	306		
8" UNIF. CONC. DR-6 SQ.YDS.		100		
TEST CORES EA.	3			
SIDEWALK 4" SQ.FT.		684		
		1W		
MANHOLES ADJUST		3S		
MANHOLES COVER		-		
MANHOLES RE-CONSTRUCT		6		
BASINS ADJUST				
BASINS CONSTRUCT		1		
FILL TYPE "A" CU.YD.	54	3		

HOR. SCALE	1"=100'	BOOK 1821	PAGE 1
VER. SCALE	1"=4'	DATE LEVELS 4-19-54 DRAWING 5-5-54	
PLAN PROFILE	NEW NEW	COMPUTED R.C.M.	
CHECKED W.O.	GRADE W.O.	CHECKED G.B.	
1540.60	LENGTH	770.30	
116	LENGTH	58	
1656.60	LENGTH	828.30	
	LOTS	CITY	
COST ADVERTISING			
COST INSPECTION			

DESIGNED BY W. OWENS
DRAWN BY Jas. Wyatt
TRACED BY
CHECKED BY J.R. BEHM
APPROVED Behm
W.J. Wallace
M. Fitzpatrick
ASSISTANT CITY ENGINEER

INDEX NO. 73 TOPO NO. 121
RECORD NO.

CONTRACT NO. PW-2767-W

DEPARTMENT OF PUBLIC WORKS DETROIT
CITY ENGINEER'S OFFICE — DIVISION OF PAVING DESIGN

STREET PAVING PLAN

325-CJ-1
PETITION NO. 6036

NAME OF STREET **FENTON**
FROM 8' S - N.P.L. PURITAN
TO N.P.L. OF FLORENCE

SHEET 1
1" = 50' SHEETS

TYPE OF PAVEMENT R.C.C. CONCRETE - INTEGRAL CURB TYPE II WIDTH 30'
8" UNIFORM AT STREET INTERSECTIONS EXCEPT AS NOTED

CONTRACT APPROVED

SEWERS-12" LIN.FT. 10

770.30' — 379.3 — 770.30'

YOST SCHOOL

848.30' — 848.60'

50' PW 2766 W

50' PW 2766 W

C.G. 141.30

8" Unif. Conc. Type II Curb.

21" Pipe — 18" Pipe — 15" Pipe

Inv. 132.00 — Inv. 130.80 — Inv. 130.28

NOT IN THIS CONTRACT

DRAINAGE TO BE INSTALLED BY OTHERS BEFORE FENTON IS PAVED

BARTON-WAYBURN BLDG. CO. 7-5-55

STUB INV. 130.20

UNDER-CONTRACT P.W. 2436 W

Inv. 130.84 M.H. Inv. El. 130.50

Inv. 128.88

PURITAN — No Grade Set — Redford Twp.

FLORENCE — PW. 2766 W

GROVE — No Grade Set

BENCH MARKS

	ELEV.
PLBM #121-251 N.E. Cor. Puritan & S-Points	144.825
Arrow On Hyd. S.W. Cor. Florence & Fenton	145.00
Arrow On Hyd. S.E. Cor. Fenton & Grove	144.06
PLBM #122-250 N.E. Cor. S-Points & G Mile	158.055

NOTES

FOR SYMBOLS A ETC., SEE STD. DRAW'G. C-327
HORIZONTAL CONTROL BY EXIST'G. STAKES.

TREE SCHEDULE

Sta	No	Size	Type	Location
0+33	1	14"	P	15.7'E. OF ℄
0+86	1	12"	P	27.5'E " " "
2+10	1	20"	P	10.6'E " " "
2+16	2	12 & 14"	TWIN	10.7'E " " "
2+95	1	60"	P	11.4'W " " "
4+05	1	10"	P	28.4E " " "
7+25	1	4"	P	15.0E " " "

93928

PURITAN 76 — FLORENCE 50' — NOT IN THIS CONTRACT — GROVE 50'

+70.3 — +48.45 ℄