SEWER OK Shipach 7/18/55

REVISIONS

OLD MAP 11-26-40 ✓

QUANTITY CHANGE DUE TO DELETION OF 220.37' OF WALK FROM CONTRACT. 10-4-55 D.B.

QUANTITY CHANGE DUE TO WALK CONSTRUCTION ON EAST SIDE OF HOUGHTON 10-7-55

SUPPLEMENTARY DETAILS

C-324A	C-390	C-587	C-739B
C-325	C-524	C-733	C-938
C-326A	C-585	C-739	C-1608
C-327	C-586	C-739A	C-1783

NOTE:
BEFORE STARTING CONSTRUCTION CONTRACTOR MUST CHECK WITH UTILITIES FOR LOCATIONS OF EXISTING STRUCTURES WHETHER OR NOT INDICATED ON PLANS.

PLAN SCALE DISTORTED
LOTS & ALLEYS 1"=60' ✓
STREET WIDTHS 1"=60' ✓

DRAINAGE COMPLETED 4-6-48 ✓

PAVING COMPLETED C.C. 6-26-56

Tree Removal
4"-12" Lots 18 ✓
13"-18" Lots 6 ✓

QUANTITIES		ESTIMATED LOTS	ESTIMATED CITY	FINAL LOTS	FINAL CITY
EXCAVATION CU. YDS.		4206 ✓	714 ✓		
NEW CURB TYPE II LIN. FT.		17 ✓	21 ✓		
PAVING 8"C-8 SQ. YDS.		8547 ✓			
8" Unif. Conc. Sq Yds			3177 ✓		
8" Unif. Conc. Sq Yds		57 ✓	61 ✓		
SIDEWALK 4" SQ. FT.		720 ✓	669 ✓		
			192 ✓		
MANHOLES	ADJUST		1 ✓		
	CONST. RE-CONSTRUCT				
BASINS	ADJUST		1 ✓		
	CONSTRUCT		15 ✓		
SEWERS-12" LIN. FT.			180 ✓		
Conc. Dr. C" Sq Ft			100 ✓		
Sidewalk Removal S.Ft.		434 ✓	72 ✓		
Drive Removal S.Ft.			60 ✓		
Test Cores		10 ✓			

HOR. SCALE 1"=60' ✓		BOOK 1801 ✓	PAGE 20 ✓		
VER. SCALE 1"=2' ✓		DATE	LEVELS 6-55 ✓		
			DRAWING 6-2-55 ✓		
PLAN W.O. W.M.	PROFILE W.M.	COMPUTED W.M.			
CHECKED J.K.	GRADE W.M.	CHECKED N.W.			
LOTS 2L	4996 71 ✓	LENGTH	249836 ✓		
CITY 2L	147 60 ✓	LENGTH	7380 ✓		
TOTAL 2L	5144 31 ✓	LENGTH	257216 ✓		
		LOTS	CITY		
COST ADVERTISING					
COST INSPECTION					

DESIGNED BY Wingfield D. Morris
DRAWN BY Wingfield D. Morris
TRACED BY
CHECKED BY J.E. BEHM
APPROVED
CITY ENGINEER

55-6 CARD NO.

INDEX NO. 71 ✓ TOPO NO. 123 ✓

RECORD NO.

CONTRACT NO. 2684W

DEPARTMENT OF PUBLIC WORKS DETROIT

CITY ENGINEER'S OFFICE --- DIVISION OF PAVING DESIGN

STREET PAVING PLAN

NAME OF STREET HOUGHTON ✓

ASSIGN. NO. 326 BP 22 ✓
PETITION NO. 5565 ✓ 853 ✓

FROM 138' S. OF N.P.L. OF SEVEN MILE ✓

TO 953.04'℄ N. OF N.P.L. OF SEVEN MILE ✓

SHEET 1 OF 3" SHEETS

TYPE OF PAVEMENT B. B. B. ONE COURSE CONCRETE - INTEGRAL CURB WIDTH 30'

8" UNIFORM AT STREET INTERSECTIONS EXCEPT AS NOTED

CONTRACT APPROVED CC TO $

PETITION 5565 LAWRENCE DRESNER . . . . . 5-5-53 ✓
PETITION 853 MRS. W.M. ANDERSON . . . . . 3-30-54 ✓

DUBOIS SCHOOL
SEE SHEET 3
951.44'

953.64'

REMOVE EXISTING DRIVE AND WALK APPROXIMATELY 60' AND 78 SQ. FT. RESPECTIVELY

CONSTRUCT 6' WALKS ONE FOOT OFF PROPERTY LINE FROM SEVEN MILE ROAD TO STA 2+50

SEVEN MILE ROAD 66'

BENCH MARKS

P.L.B.M. 115-250
167' W. OF N.W. COR. 7 MILE & LAHSER . . 154.621
C.B.M.
NAIL IN POLE S. SIDE 7 MILE @ PP HOUGHTON . 156.12
C.B.M.
ARR ON HYD. E. SIDE OF HOUGHTON STA 3+81 . . . 158.62
C.B.M.
ARR ON HYD. E. SIDE OF HOUGHTON STA. 8+27 . . . 159.25
P.L.B.M. 115-251
N.E. COR. LAHSER & PEMBROKE . . . 160.479

HORIZONTAL CONTROL

+ IN SIDEWALK 5' OFF P.L. (EXCEPT AT SEVEN MILE WHICH IS 25.01') ON THE EAST SIDE.

NOTES: FOR SYMBOLS Ⓐ ETC., SEE DET. DRWG. C-327

AT Ⓡ REMOVE 1434.5 SQ. FT. OF EXIST WALK ✓

NO. 1 QUANTITY CHANGE 10-4-55
DUE TO DELETION OF WALK FROM CONTRACT LOTS
SIDEWALK 4" — 720 SQ FT D.B.

TREE SCHEDULE

STATION	SIZE	NUMBER	LOCATION
0+11	4"	2	45.1' W. E.P.L.
0+58	6"	1	45.1' W. E.P.L.
1+30	12"	1	45.1' W. E.P.L.
2+38	16"	1	33.3' W. E.P.L.
0+39	6"	1	50.1' W. E.P.L.
0+29	6"	1	49.3' W. E.P.L.
0+23	8"	1	49.3' W. E.P.L.
0+45	8"	1	49.3' W. E.P.L.
0+49	8"	1	49.3' W. E.P.L.
0+88	6"	1	50.10' W. E.P.L.
1+04	8"	1	50.10' W. E.P.L.

NO. 2 QUANTITY CHANGE 10-7-55
DUE TO WALK CONSTRUCTION ON EAST SIDE OF HOUGHTON, SEVEN MILE TO STA 2+50
CITY:
SIDEWALK 4" + 1626 SQ. FT. P.B.

94491