

CONTRACT NO. P.W. 1098

DEPARTMENT OF PUBLIC WORKS DETROIT
CITY ENGINEER'S OFFICE - DIVISION OF PAVING DESIGN
STREET PAVING PLAN

325 AE-15
ASSIGN NO. 325W43
REVISED NO. 8346
8408

LINDSAY
S.P.L. OF FARGO
30' N. OF S.P.L. OF 8 MILE RD.

INDEX TOPO NO. 50-2
NO. 63 105
RECORDED NO.
SHEET 1 OF 1
WIDTH 30'36"

DESIGNED BY: Scarlen
DRAWN BY: KANSMAN
TRACED BY: HK
CHECKED BY: Robert R. Barton
APPROVED BY: W.J. Wallace
CITY ENGINEER

BOOK 1003 PAGE 67
DATE DRAWING 5-26-49
COMPUTED P.B.
CHECKED 5.5.
LENGTH 1 684.75
CITY 230
TOTAL 1 914.75

QUANTITIES ESTIMATED FINAL

QUANTITIES	ESTIMATED	FINAL
EXCAVATION CU. YDS.	2514	508
NEW CURB LIN. FT.	59	69
PAVING 8" B. SQ. YDS.	5870	137
9 UNIF. CONC. DRIVES	1072	1072
4" SO. ST. SIDEWALK	144	144
MANHOLES RECONSTRUCT	3	2
ADJUST	2	2
BASINS	12	12
SEWERS 12" LIN. FT.	1070	995
CONSTRUCT	13	13

NOTE: BEFORE STARTING CONSTRUCTION CONTRACTOR MUST CHECK WITH UTILITIES FOR LOCATIONS OF EXISTING STRUCTURES WHETHER OR NOT INDICATED ON PLANS.
PLAN SCALE DISTORTED
LOTS & ALLEYS 1" = 100'
STREET WIDTHS 1" = 100'
DRAINAGE COMPLETED
PAVING COMPLETED C.C. 10-24-50

REVISIONS NOTES

NO.	DATE	DESCRIPTION	
C-324A	C-390	C-587	C-739B
C-325	C-524	C-733	C-938
C-326A	C-585	C-739	
C-327	C-586	C-739A	

