SEWER	OK Jhiepah.
INDEXED	
REVISIONS	

JOB NO.		PROGRESS	
BLUE PRINT ISSUED FOR:	DATE	START	FINISH
GRADE ONLY			
CATCH BASINS			
PAVING-CLASS-			
DEPT. OF WATER SUPPLY			
GAS CO.			

QUANTITIES	LOTS	CITY	LOTS	CITY
EXCAVATION				
STRAIGHT CURB NEW				
OLD CURB RESET				
CIRCULAR CURB				
PAVING				
CONCRETE BASE				

HOR. SCALE	1"=100'
VER SCALE	1"=2'
BOOK	872 PAGE 63
DATE	OCT. 16. 1940
PLAN	M.J.M
PROFILE	M.J.M
COMPUTED	
CHECKED	H.J.S
GRADE	V.G.W.S
CHECKED	

LOTS 2L.	2,343	45	LENGTH 1171.72
CITY 2L.	303	00	LENGTH 151.50
TOTAL 2L.	2,646	45	LENGTH 1323.22
			LOTS / CITY
COST ADVERTISING BLANKS			
COST INSPECTION			

DESIGNED BY	M.J. MORGAN
DRAWN BY	M.J. MORGAN
TRACED BY	
CHECKED BY	
APPROVED	

W. J. Wallace
ENGINEER OF STREETS
Martin R. Fisher
ASS'T CITY ENGINEER

CARD NO

INDEX NO	TOPO NO

RECORD NO

DEPARTMENT OF PUBLIC WORKS DETROIT

CITY ENGINEER'S OFFICE --- DIVISION OF PAVING DESIGN

STREET PAVING PLAN

NAME OF STREET MONTE VISTA

FROM MARGARETA

TO 7 MILE RD.

TYPE OF PAVEMENT 2½" OIL AGG ON 6" CONC BASE WIDTH 30'

Est - 10-28-40 - SERIES S-1

NUMBER OF SHEETS

SHEET NO

DESIGNED BY	M.J. MORGAN	APPROVED
DRAWN BY	M.J. MORGAN	
TRACED BY		ENGINEER OF STREETS
CHECKED BY		ASS'T CITY ENGINEER

B.M.- TRACK SPIKE IN POLE S.E. COR GRIGGS & CURTIS → 191.34

B.M.- NAIL IN POLE N.W. COR PICKFORD & MONTE VISTA → 191.13

B.M.- NAIL IN 30" OAK N.E. COR MARGARETA & MONTE VISTA → 192.20

B.M.- HYD N.E. COR. SEVEN MILE RD & MONTE VISTA → 194.68

JOB-NO-D-2062

TREES IN STREET AFFECTED BY NEW PAVEMENT

18" OAK 25.5 5+62
24" TWIN OAK 17.5 4+78
4" OAK 23.5 4+67
14" OAK 12.7 2+89
36' PVMT 12'
16.6 0+45
12" OAK 0+00
MONTEVISTA AVE'
6' WALK 6'
CLARITA
7 MI Rd
MARGARETA
GOST
WEST CURB
EAST LINE
18" OAK 18.5 4+81
18" OAK EAST CURB 15.7 1+67
9" OAK 18.2 1+40
9" OAK 18.6 1+32
36' PVMT 12'
0+00

MARGARETA
MH BOT 185.50
190.70
GRACE HOSPITAL
790.39 CALC
CLARITA
THEATRE
372.95 CALC
SEVEN MILE RD
86'-0" CNTR
23' 8" WATER
192.40
192.80
12" CONCR. 8.9
8.2 12" VIT 9.8 15" VIT. 12.7 18" VIT 13.5 20" VIT 13.2
44.70 40 51 49 47 45 43 41 39 37 44.70 44.81
50.71 50 50 40 36 34 32 30 28 26 40 50.14
12" CONC. 8.6
8.2 12" CR. 609.40 112' 15" CR.
13.2 18" CR. 590.71
6' WKS 6' FROM P.L. EAST SIDE ONLY
24" CR. 100 25 24 20' CR.
8" WATER 12" GAS 15'
Rebuild Walks on E. Side of Monte Vista
18' JOG IN WLKS
CATCH BASINS
RELIEF BASES
RELIEF BASINS AT P.L.
190.98 191.18 191.08 191.55 191.95 192.35 191.95 192.55 193.12 193.32 193.52 193.30 193.22 193.10 192.66 192.86 192.76 192.50 192.30 192.32 191.80 192.02 191.64 191.64 191.65 191.85
190.80 190.90 190.80 191.70 192.40 193.30 193.10 192.50 191.80 191.40 191.90
SEE PLAN
201.90
CLARITA EAST
CLARITA WEST
192.00 191.00 190.00
191.79 191.66 191.55 191.80 191.22 191.30 191.52 191.12 190.59 190.89
129.82 31.5
0 1 2 3 4 5 6 0 1 2 3 4 5 6

PAVING SECTION

18'-0" 4'-6" 4'-6" 4'-6" 4'-6"
7" 6" 2" 10½" 0¼"
2½" OIL AGG
6" CONCRETE

GRADING SECTION

18'-0" 4'-6" 4'-6" 4'-6" 4'-6"
5½" 10½" 9½" 8½"
+ = 0.825