4-18 Pm 6-44

SEWER	O.K. J. Siegel
INDEXED	
REVISIONS	

JOB NO.		PROGRESS	
BLUE PRINT ISSUED FOR:	DATE	START	FINISH
GRADE ONLY			
CATCH BASINS			
PAVING-CLASS-			
DEPT. OF WATER SUPPLY			
GAS CO.			

QUANTITIES	LOTS	CITY	LOTS	CITY
EXCAVATION				
STRAIGHT CURB NEW				
OLD CURB RESET				
CIRCULAR CURB				
PAVING				
CONCRETE BASE				

HOR. SCALE	1"=100'	BOOK 1384 PAGE 35	
VER SCALE	1"=2'	DATE 12-26-40	
PLAN		PROFILE	COMPUTED
CHECKED		GRADE	CHECKED

		LENGTH		
LOTS	2L	3 415.14	LENGTH	~~1 707.07~~
CITY	2L	~~146.00~~	LENGTH	~~73.00~~
TOTAL	2L	~~3 561.14~~	LENGTH	~~1 780.07~~
			LOTS	CITY
COST ADVERTISING BLANKS				
COST INSPECTION				

DESIGNED BY	H. Smart
DRAWN BY	F. Minikel
TRACED BY	
CHECKED BY	

APPROVED

Robt. G. Brown

L. V. Wallace
ENGINEER OF STREETS

Martin R. Fisher
HOIST CITY ENGINEER

CARD NO ○

RECORD NO ○

DEPARTMENT OF PUBLIC WORKS DETROIT

CITY ENGINEER'S OFFICE — DIVISION OF PAVING DESIGN

STREET PAVING PLAN

INDEX NO	TOPO NO
63	104

NAME OF STREET ROSEMONT RD. 60'+120'W°

FROM PICKFORD

TO SEVEN MILE ROAD (23' N. of S.L.)

NUMBER OF SHEETS 1

SHEET NO 1

TYPE OF PAVEMENT 6" ONE COURSE CONCR. WIDTH 30 & 36

Pet. #4416 - W.B. BLACKINTON, ET. AL, C.C. - 4-27-43 - G.O. #25941.

NOTE - CONSTRUCT RETURNS WITH 10 FT. WIDENING. - SEE SPECIAL DETAIL - CONC. SLAB IN 7 MI RD TO BE 10" THICK.

BENCH MARKS

B.M. NAIL IN POLE N.W. CORNER ROSEMONT AND PICKFORD ---- ELEV. ---- 175.10

B.M. 5" IN LOT # 775 S.W. COR. ROSEMONT AND MARGARETA ---- ELEV. ---- 176.28

B.M. 8" IN LOT # 789 N.E. COR. CLARITA AND ROSEMONT ---- ELEV. ---- 178.16

B.M. NAIL S.S. LT. POLE S.W. COR. ROSEMONT + SEVEN MILE RD. ---- ELEV. ---- 180.91

Contract Limits Pet. #4416 - 781.99

By D.P.W.

No Drainage Rockford

DRAINAGE COMPLETED 4-30-43 ACCEPTED 6-1-44

PAVING COMPLETED 4-30-43 ACCEPTED 6-1-44

180.26 179.92 FUTURE CURB 179.79