DEPARTMENT OF PUBLIC WORKS — DETROIT

CONTRACT PW 618

CITY ENGINEER'S OFFICE — DIVISION OF PAVING DESIGN

STREET PAVING PLAN

SYRACUSE

N.P.L. NEVADA ✓

S.P.L. ROBINWOOD ✓

325 I-18

~~AP 172~~

NUMBER OF SHEETS	SHEET NO.
1	1

CARD NO. ✓

INDEX NO.	TOPO. NO.
19	53

RECORD NO.

FROM

TO

NAME OF STREET

TYPE OF PAVEMENT 8" UNIFORM AT STREET INTERSECTION 8:6:8 ONE COURSE CONC. - INTEGRAL CURB

WIDTH 26-28-30

PET. #5509 A. SKONIECZNY ET AL. 6/10/47

DESIGNED BY	E. T. Stefula
DRAWN BY	E. T. Stefula
TRACED BY	E. T. S.
CHECKED BY	GS. R3
APPROVED	[signature] ENGINEER OF STREETS
	Martin R. Taylor ASSIST. CITY ENGINEER

PROGRESS	START	FINISH

LOTS	CITY
231 ✓	195 ✓
240	228 60 ✓
15 ✓	7 ✓
3	
231 ✓	195 ✓
316 ✓	238 28 ✓
16	4 ✓
5	

QUANTITIES	LOTS	CITY
EXCAVATION CU. YDS.	2,310 ✓	
STRAIGHT CURB NEW		
SIDEWALKS LIN. FT.		
PAVING 8:6:8 SQ. YDS.	5,396 ✓	
PAVING 8" UNIF. SQ. YDS.		
SEWERS 12" LIN. FT.		
M. H'S - ADJUST		
C.B'S - ADJUST		
C.B'S - CONSTR.		

	LOTS	CITY
LENGTH	1,793.33	
LENGTH	50.00	
LENGTH	843.33	

	LOTS	CITY
COST ADVERTISING BLANKS	89.67 ✓	2.50 ✓
COST INSPECTION	448.33 ✓	12.50 ✓

HOR. SCALE	1"=50'
VER. SCALE	1"=2' / 1"=100'
DATE	OCT. 23-1943
BOOK	1558 PAGE 28

	PLAN	PROFILE	COMPUTED
CHECKED	EES	EES	GS
	GRADE		CHECKED
	EES ~~EES~~		R²

	LOTS 2L	CITY 2L	TOTAL 2L
	3	100	3
	586	00	686
	65 ✓	00 ✓	65 ✓

SEE CURVE DET.

NOTES:

- (A) RECONSTRUCT 3 EXISTING S.M.H. BASINS, AT CURB LOCATION, WITH 3-18"x12" Y FLAT TYPE BASINS, CONNECT TO EXISTING OUTLETS AS SHOWN.
- (C) ADJUST TOPS OF 15 EXISTING S.M.H. BASINS WITH FLAT TYPE GRATES & FRAMES.
- (X) CONTRACTOR SHALL REMOVE CONCRETE HEADER & BROKEN ASPHALT BACK OF JUNCTION AS REQ'D & FILL WITH COLD PATCH TO MEET NEW GRADES. 40 CU. YDS HAVE BEEN INCLUDED UNDER EXCAVATION TOTALS FOR COST.
- (W) CONSTRUCT 240 SQ. FT. OF STANDARD 4" SIDEWALK. ✓

18 EX. S.M.H. BASINS 5-27-43

DRAINAGE COMPLETED.....

C.C.

PAVING COMPLETED 1-4-49.....

PLAN SCALE DISTORTED

LOT AND ALLEY DIMENSIONS - 1"=100'

ST. WIDTH & INTERSECTIONS - 1"=50'

BENCH MARKS

ARROW ON HYD. W.S. SYRACUSE ± 35' N. OF NEVADA	148.43 ✓
" " " " " " ±480' " " "	147.63 ✓
" " " " " " ±265' N. OF STOCKTON	146.55 ✓
" " " N.W. COR. " ℄ HILDALE	146.60 ✓
" " " S.E. COR. " ℄ ROBINWOOD	146.73 ✓

A - CRACKED & BROKEN WK.

E - ELM TREE

M - MAPLE "

IN THIS BLOCK THE WALKS ARE RAISED FROM 2" TO 4" AT ALMOST EVERY LARGE TREE.

Circle Change 10/1/48