# FAIRWAY ENGINEERING LLC

Land Development-Geotechnical-Structural 28525 Beck Road, Suite 124 Wixom, MI 48393

June 6, 2021

## Fabio Giske

Facilities Director | Princeton Management

2550 Telegraph rd., Suite 200 | Bloomfield Hills, MI 48302

Main: (248) 683-2500 | Fax: (248) 633-2390

E-mail: f.giske@prinmgmt.com

Re: Sidewalk Repair Review

Claridge

1514 Washington Blvd

Detroit, MI

Dear Mr. Giske:

Per your request, we visited the above referenced site on June 2<sup>nd</sup>, 2021. The purpose of the site visit to review sidewalk repair location and support under the sidewalk. Attached are some photographs of the site taken during site visit. Previously we had visited the same site in 2019 and prepared a support plan for the sidewalk which is attached.

The sidewalk is supported by glass and steel framing form the original building construction. Under the sidewalk the building basement is extended. Overtime the surface material/asphalt patches have deteriorated. Current plan is to repair and recap the sidewalk. Recap consist of cleaning the area, remove asphalt debrie and repatch with concrete.

In 2019 we had prepared a plan to support the sidewalk framing from underside as additional support system (to the original framing system). Attached are calculation of r the steel beam and support columns. The columns are supported or either existing concrete platform for utilities and/or floor slab of the building. The maximum spacing of the posts is 8 feet and carry partial load from the sidewalk. The system was installed in 2019 with steel plate and beams and columns per plan.

Based on current field condition review, the column bases are in same condition and adequate for the purpose as it installed. The beams were designed to carry full concrete sidewalk load. Since the original framing is integral to the building foundation and to exterior wall along the sidewalk, it is planned to leave in place, clean up the damaged areas, recap the damaged asphalt with concrete. Based on the field conditions observed and our calculations, it is our opinion that current plan for sidewalk recap is adequate with leaving support system in place.

This report is based on the field observations made during site visit and information gathered from the site and verbal information provided to us. The information provided in this report addresses the limited objectives related to the inspection of the subject property and provide documentation. This report describes the conditions present at the time of report preparation and is based upon the observations made. This report is not intended to fully delineate or document every defect or deficiency throughout the subject property. If any additional information or evidence becomes available at later date, Fairway Engineering LLC reserves the right to amend this report and modify our recommendations as necessary at additional cost. If you have any questions or need additional information, please contact us.

Sincerely,

# **FAIRWAY ENGINNERING LLC**

Madhukar D. Mahajan, P.E.

President/Owner

Enclosures:

Site Photographs, beam calculations, drawing of the support system


# 1514 WASHINGTON BLVD DETROIT, MI



























TYPICAL CROSS SECTION OF SIDEWALK DECK





NO. DATE ADDENDUM/BULLETIN

**APARTMENTS** 

CLARIDGE / **H** 

ZACK M OSTROFF & ASSOCIATES
RESIDENTIAL/COMMERCIAL DESIGNER/PLANNER
web: www.zoarchitecture.com
email: zack@zoarchitecture.com
DH.248.425.4190

THIS DRAWING AS AN INSTRUMENT OF SERVICE IS AND SHALL REMAIN THE PROPERTY OF THE DESIGNER AND SHALL NOT BE USED IN ANY WAY WITHOUT THE PERMISSION OF THE DESIGNER. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND EXISTING CONDITIONS AT THE SITE BEFORE PROCEEDING WITH EACH PHASE OF HIS WORK.

PROPOSED BASEMENT SIDEWALK REPAIR

SHEET SCALE AS NOTED

18-039

04.24.19

FAIRWAY ENGINEERING LLC 28525 BECK ROAD, SUITE 124 WIXOM, MI 48393

Project Title: Claridge

Engineer: Project ID: Project Descr:

Printed: 1 JUN 2018, 9:00AM

**Steel Beam** 

File = C:\Users\costcopc\DOCUME~1\ENERCA~1\claridge.ec6

Licensee: FAIRWAY ENGINEERING, LLC

Lic. #: KW-06007140

Description: DECK BEAM

## **CODE REFERENCES**

Calculations per AISC 360-10, IBC 2012, CBC 2013, ASCE 7-10

Load Combination Set: ASCE 7-10

### **Material Properties**

Analysis Method : Allowable Strength Design

Beam Bracing: Beam is Fully Braced against lateral-torsional buckling

Bending Axis: Major Axis Bending

Fy: Steel Yield: 36 ksi E: Modulus: 29,000.0 ksi

D(0.15) L(0.12) S(0.05)

W6x9

Span = 6.50 ft

## **Applied Loads**

Service loads entered. Load Factors will be applied for calculations.

Beam self weight calculated and added to loading

Uniform Load: D = 0.0750, L = 0.060, S = 0.0250 ksf, Tributary Width = 2.0 ft, (Side walk load)

**DESIGN SUMMARY Design OK** Maximum Bending Stress Ratio = 0.135:1 Maximum Shear Stress Ratio = 0.064:1 Section used for this span **W6x9** Section used for this span W6x9 Ma: Applied 1.514 k-ft Va: Applied 0.9315 k Mn / Omega: Allowable 11.192 k-ft Vn/Omega: Allowable 14.443 k Load Combination +D+0.750L+0.750S+H Load Combination +D+0.750L+0.750S+H 0.000 ft Location of maximum on span 3.250ft Location of maximum on span Span # where maximum occurs Span # 1 Span # where maximum occurs Span # 1 Maximum Deflection Max Downward Transient Deflection 0.010 in Ratio = 7,661 >= 3600.010 in Ratio = Max Upward Transient Deflection 7,661 >= 360 0.024 in Ratio = Max Downward Total Deflection 3208 >=180 Max Upward Total Deflection 0.000 in Ratio = 0 < 180

**Maximum Forces & Stresses for Load Combinations** 

Load Combination		Max Stress Ratios			Summary of Moment Values							Summary of Shear Values		
Segment Length	Span #	М	V	Mmax +	Mmax -	Ma Max	Mnx	Mnx/Omega	Cb	Rm	Va Max	Vnx	Vnx/Omega	
+D+H														
Dsgn. L = 6.50 ft	1	0.075	0.036	0.84		0.84	18.69	11.19	1.00	1.00	0.52	21.66	14.44	
+D+L+H														
Dsgn. L = 6.50 ft	1	0.132	0.063	1.47		1.47	18.69	11.19	1.00	1.00	0.91	21.66	14.44	
+D+Lr+H	_						40.40							
Dsgn. L = 6.50 ft	1	0.075	0.036	0.84		0.84	18.69	11.19	1.00	1.00	0.52	21.66	14.44	
+D+S+H	1	0.000	0.047	1.10		1 10	10.40	11 10	1 00	1 00	0.40	21 //	1111	
Dsgn. L = 6.50 ft +D+0.750Lr+0.750L+H	ı	0.099	0.047	1.10		1.10	18.69	11.19	1.00	1.00	0.68	21.66	14.44	
Dsgn. L = 6.50 ft	1	0.118	0.056	1.32		1.32	18.69	11.19	1 00	1.00	0.81	21.66	14.44	
+D+0.750L+0.750S+H	'	0.110	0.050	1.32		1.52	10.07	11.17	1.00	1.00	0.01	21.00	14.44	
Dsgn. L = 6.50 ft	1	0.135	0.064	1.51		1.51	18.69	11.19	1.00	1.00	0.93	21.66	14.44	
+D+0.60W+H	•													
Dsgn. $L = 6.50 \text{ ft}$	1	0.075	0.036	0.84		0.84	18.69	11.19	1.00	1.00	0.52	21.66	14.44	
+D+0.70E+H														
Dsgn. L = 6.50 ft	1	0.075	0.036	0.84		0.84	18.69	11.19	1.00	1.00	0.52	21.66	14.44	
+D+0.750Lr+0.750L+0.450W+	·H													
Dsgn. $L = 6.50 \text{ ft}$	1	0.118	0.056	1.32		1.32	18.69	11.19	1.00	1.00	0.81	21.66	14.44	
+D+0.750L+0.750S+0.450W+	Η .													
Dsgn. L = 6.50 ft	1	0.135	0.064	1.51		1.51	18.69	11.19	1.00	1.00	0.93	21.66	14.44	
+D+0.750L+0.750S+0.5250E+	-H	0.125	0.074	1 51		1 51	10 (0	11 10	1 00	1.00	0.00	21 //	1111	
Dsgn. L = 6.50 ft	Ţ	0.135	0.064	1.51		1.51	18.69	11.19	1.00	1.00	0.93	21.66	14.44	
+0.60D+0.60W+0.60H Dsgn. L = 6.50 ft	1	0.045	0.021	0.50		0.50	18.69	11.19	1 00	1.00	0.31	21.66	14.44	
DSyll. L = 0.30 II	ı	0.043	U.UZ I	0.50		0.30	10.09	11.19	1.00	1.00	0.51	∠1.00	14.44	

FAIRWAY ENGINEERING LLC 28525 BECK ROAD, SUITE 124 WIXOM, MI 48393

Project Title: Claridge Engineer: Project ID: Project Descr:

Printed: 1 JUN 2018, 9:00AM

Steel Beam								File = C:\l	Users\c	ostcopc\D	OCUME~1\EN	ERCA~1\cl	aridge.ec6
Lic. # : KW-06007140								Lice	ensee	: FAIR	RWAY ENG	INEER	ING, LLC.
Description : DECK BEA	M												
Load Combination		Max Stres	ss Ratios		S			Summ	Summary of Shear Values				
Segment Length Sp	oan #	M	V	Mmax +	Mmax -	Ma Max	Mnx	Mnx/Omega	Cb	Rm	Va Max	Vnx	Vnx/Omega
+0.60D+0.70E+0.60H Dsgn. L = 6.50 ft	1	0.045	0.021	0.50		0.50	18.69	11.19	1.00	1.00	0.31	21.66	14.44
<b>Overall Maximum D</b>	eflec	ctions											
Load Combination		Span	Max. "-" Defl	Location	n in Span	Load Combination			Max. "+" Defl		Location in Span		
+D+0.750L+0.750S+0.5250E-	+H	1	0.0243		3.269						0.0000		0.000
Vertical Reactions					Support	Support notation : Far left is #1			Values in KIPS				
Load Combination		Support 1	Support 2										
Overall MAXimum		0.932	0.932										
Overall MINimum		0.163	0.163										
+D+H		0.517	0.517										
+D+L+H		0.907	0.907										
+D+Lr+H		0.517	0.517										
+D+S+H		0.680	0.680										
+D+0.750Lr+0.750L+H		0.810	0.810										
+D+0.750L+0.750S+H		0.932	0.932										
+D+0.60W+H		0.517	0.517										
+D+0.70E+H		0.517	0.517										
+D+0.750Lr+0.750L+0.450W+	+H	0.810	0.810										
+D+0.750L+0.750S+0.450W+	-H	0.932	0.932										
+D+0.750L+0.750S+0.5250E-	+H	0.932	0.932										
+0.60D+0.60W+0.60H		0.310	0.310										
+0.60D+0.70E+0.60H		0.310	0.310										
D Only		0.517	0.517										
Lr Only													
L Only		0.390	0.390										
S Only		0.163	0.163										
W Only													
E Only													
H Only													