

CITY OF DETROIT, WAYNE COUNTY, MICHIGAN



GENERAL NOTES

UTILITIES

UNDERGROUND UTILITIES / MISS DIG
FOR PROTECTION OF UNDERGROUND UTILITIES AND IN CONFORMANCE WITH PUBLIC ACT 174, 2013, THE CONTRACTOR SHALL DIAL 1-800-482-7171 A MINIMUM OF THREE FULL WORKING DAYS, EXCLUDING SATURDAYS, SUNDAYS, AND HOLIDAYS PRIOR TO BEGINNING EACH EXCAVATION IN AREAS WHERE PUBLIC UTILITIES HAVE NOT BEEN PREVIOUSLY LOCATED. MEMBERS WILL THUS BE ROUTINELY NOTIFIED. THIS DOES NOT RELIEVE THE CONTRACTOR OF THE RESPONSIBILITY OF NOTIFYING UTILITY OWNERS WHO MAY NOT BE A PART OF THE "MISS DIG" ALERT SYSTEM

IF PLAN INFORMATION INDICATES AN EXISTING UNDERGROUND UTILITY IS OR WILL BE OUT OF SERVICE WITHIN THE LIMITS OF THIS CONTRACT, THE CONTRACTOR IS CAUTIONED TO TREAT SUCH A LINE AS IF IT WERE STILL IN SERVICE AND NOTIFY "MISS DIG" WHEN WORKING IN THE AREA OF THE OUT OF SERVICE FACILITY.

EXISTING WATER MAINS AND SEWERS
THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO PROPERLY IDENTIFIED EXISTING WATER MAINS AND/OR EXISTING SEWERS DURING THE CONSTRUCTION OF THIS PROJECT.

DETAILED GRADES

SIDEWALK AND SIDEWALK RAMP GRADES
ALL SIDEWALK AND SIDEWALK RAMP GRADES SHALL BE STAKED ACCORDING TO STANDARD PLAN R-28 SERIES AND AS SHOWN ON THE PLANS. PRIOR TO CONSTRUCTING THE SIDEWALK AND SIDEWALK RAMPS, THE ENGINEER WILL VERIFY THE GRADES AND AUTHORIZE THE CONSTRUCTION OF THE SIDEWALK AND SIDEWALK RAMPS.

EARTHWORK

EARTH DISTURBANCE LIMITS
THE EARTH DISTURBANCE LIMIT FOR THIS PROJECT WILL BE LIMITED TO 10' BEYOND THE SLOPE STAKE LINE OR TO THE ROW LINE WHICHEVER IS LESS FOR ALL AREAS EXCEPT FOR WETLAND AREAS. RESTORATION MEASURES HAVE BEEN INCLUDED IN THIS SET OF PLANS FOR THE APPROVED AREAS OF DISTURBANCE. THE CONTRACTOR SHALL SUBMIT AN EARTH CHANGE PLAN FOR ANY WORK BEYOND THE APPROVED LIMITS TO THE ENGINEER TO REVIEW FOR APPROVAL PRIOR TO THE DISTURBANCE. ALL COSTS FOR OBTAINING AND EXECUTING AN APPROVED EARTH CHANGE PLAN, INCLUDING RESTORATION, SHALL BE AT THE CONTRACTOR'S EXPENSE.

SOIL EROSION MEASURES
APPROPRIATE SOIL EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE IN PLACE PRIOR TO EARTH-DISTURBING ACTIVITIES. PLACE TURF ESTABLISHMENT ITEMS AS SOON AS POSSIBLE ON POTENTIAL ERODABLE SLOPES AS DIRECTED BY THE ENGINEER.

BASES

AGGREGATE BASE
AGGREGATE BASES SHALL BE 21AA AGGREGATE UNLESS OTHERWISE SPECIFIED.

PROJECT BENCHMARKS

VERTICAL DATUM: CITY OF DETROIT

SITE BENCH MARK NO. 2 (BAGLEY AVENUE)
SET ARROW ON HYDRANT (1977) LOCATED AT THE SOUTH SIDE OF BAGELY AVENUE AT THE 14TH STREET INTERSECTION.
ELEV. = 126.67'

SITE BENCH MARK NO. 4
ARROW ON HYDRANT AT THE NORTHEAST CORNER OF 15TH STREET AND MARANTETTE STREET
ELEVATION = 120.62'

SITE BENCH MARK NO. 5
ARROW ON HYDRANT AT THE SOUTHWEST CORNER OF 14TH STREET AND DALZELLE STREET.
ELEVATION = 122.67'

SITE BENCH MARK NO. 6
SET MAG NAIL IN THE NORTHERLY FACE OF A LIGHT POLE LOCATED AT THE SOUTHWEST CORNER OF 14TH STREET AND MARANTETTE STREET.
ELEVATION = 118.68'

SITE BENCH MARK NO. 13
SET NAIL IN THE NORTH FACE OF A LIGHT POLE AT THE SOUTHWESTERLY CORNER OF WABASH STREET AND DALZELLE STREET.
ELEVATION = 120.46'

SITE BENCH MARK NO. 14
ARROW ON HYDRANT (1979) AT THE SOUTHEASTERLY CORNER OF DALZELLE STREET AND VERMONT STREET.
ELEVATION = 121.50'

SITE BENCH MARK NO. 15
SET NAIL IN THE NORTH FACE OF A UTILITY POLE AT THE SOUTHWESTERLY CORNER OF DALZELLE STREET AND ROSA PARKS BOULEVARD.
ELEVATION = 119.50'

MISCELLANEOUS QUANTITIES

- 1 LS MOBILIZATION, \$XX,000
- XX CYD SUBGRADE UNDERCUTTING, TYPE II
- 1 LS PROJECT CLEANUP
- XX TON MAINTENANCE GRAVEL
- XX MO FIELD OFFICE, CL 3
- XX DLR FIELD OFFICE, UTILITY FEES
- 1 LS CONTRACTOR STAKING
- XX HR STAKING PLAN ERRORS AND EXTRAS, ONE PERSON
- XX HR STAKING PLAN ERRORS AND EXTRAS, TWO PERSON
- 1 LS MINOR TRAF DEVICES
- 1 LS TRAFFIC REGULATOR CONTROL

PUBLIC UTILITIES

NAME OF OWNER	TYPE OF UTILITY
PUBLIC LIGHTING AUTHORITY 65 CADILLAC SQUARE, SUITE 3100 DETROIT, MI 48226 MUKESH PATEL: 313.324.8290 EMAIL: mpatel@pldetroit.org	STREET LIGHTING
CITY OF DETROIT DETROIT WATER AND SEWERAGE DEPARTMENT 6425 HUBER DETROIT, MI 48211 EMERGENCY: 313.267.1333 EMAIL: syed.ail@detroitmi.gov SYED: 313.267.8000	WATER MAINS AND SEWERS
CITY OF DETROIT TRAFFIC ENGINEERING DIVISION – DPW 2633 MICHIGAN AVENUE DETROIT, MI 48207 PRASAD NANNAPANENI: 313.628.5603 FAX: 313.224.1304 EMAIL: PrasadN@detroitmi.gov MEENA ANTANI: 313.628.5640 EMAIL: antanim@detroitmi.gov	PAVEMENT MARKINGS, TRAFFIC SIGNALS, AND SIGNS
SIGN SHOP 2425 FENKELL DETROIT, MI 48238 PHONE: 313.628.2950 FAX: 313.628.4966	SIGN REMOVALS AND INSTALLATIONS
CITY OF DETROIT DETROIT FIRE DEPARTMENT DETROIT PUBLIC SAFETY HEADQUARTERS FIRE MARSHAL'S DIVISION & FIRE PREVENTION 1301 THIRD ST. DETROIT, MI 48226 PLAN REVIEW: 313.224.3233 CHIEF ROBINSON: 313.596.2788 EMAIL: robinsond5405@detroitmi.gov	FIRE CALL BOXES AND FIRE HYDRANTS
CITY OF DETROIT DETROIT POLICE DEPARTMENT DEPARTMENT OF PUBLIC SAFETY HEADQUARTERS 1301 THIRD ST. DETROIT, MI 48226 PHONE: 313.596.2520	POLICE
DTE / DETROIT EDISON 1 ENERGY PLAZA IGS GROUP, 5185B DETROIT, MI 48226 ROBIN O'CONNELL: 313.235.5632 FAX: 313.235.9366 EXPPOSED OR DAMAGED FACILITIES: 313.237.9567	ELECTRIC POWER
DTE / MICHIGAN CONSOLIDATED GAS COMPANY 500 GRISWOLD ST. DETROIT, MI 48226 TIM STOIAN: 734.660.8716 EMAIL: timothy.stoian@dteenergy.com KEVIN PRICE: 313.600.1884 BARBARA SAUNDERS: 313.577.7435 FAX: 313.577.7498 EXPPOSED OR DAMAGED FACILITIES: 1.800.477.4747	GAS MAINS
AT&T METRO EAST 100 S. MAIN ST, SUITE 314 MT CLEMENS, MI 48043-2374 JOE SIKOSKI: 586.466.6310 AT&T METRO WEST 31100 PLYMOUTH RD, ROOM 301 LIVONIA, MI 48150-2104 JOHN CRISPIN: 734.523.6880 FOR ADJUSTING FRAMES & COVERS	TELEPHONE
DETROIT THERMAL, LLC 3575 E. PALMER ST. DETROIT, MI 48201 ED LAROSA: 313.921.1922 FAX: 313.921.1972 EMERGENCY: 313.963.3707	STEAM LINES
COMCAST 25626 TELEGRAPH RD. SOUTHFIELD, MI 48034 GLEN YOUNGLOVE: 248.809.2712 FAX: 248.809.2721 EMAIL: Glen_Younglove@cable.comcast.com	TV CABLES

GENERAL LEGEND

	EXISTING	PROPOSED
STORM SEWER	— STM —	— — — — —
SANITARY SEWER	— SAN —	— — — — —
WATER MAIN	— W —	— — — — —
GAS MAIN	— G —	— G —
UNDERGROUND ELECTRIC LINES	— UGE —	— UGE —
UNDERGROUND TELEPHONE LINES	— UGT —	— UGT —
UNDERGROUND CABLE TELEVISION LINES	— CTV —	— CTV —
OVERHEAD LINES	— OH —	
PUBLIC LIGHTING LINES	— PLD —	
STEAM LINES	— STEAM —	
FENCE LINE	— X —	— X —
PROJECT PHASE LIMIT LINE		— — — — —
CONCRETE CURB AND GUTTER (STANDARD)		— — — — —
CONCRETE CURB AND GUTTER (REVERSED)		— — — — —
THICKENED SLAB CURB/WALK		— — — — —
STORM MANHOLE	⊕	⊙
CATCH BASIN	⊕	■
YARD BASIN		⊠
INLET BASIN		⊠
END SECTION)	▲
ROOF/DOWN SPOUT	⊗	
OVERFLOW/OUTLET STRUCTURE	⊗	●
STORM CLEAN OUT	⊗	○
SANITARY MANHOLE	⊗	●
SANITARY CLEAN OUT	⊗	●
SANITARY RISER	▲	●
SANITARY PUMP STATION	⊗	

	EXISTING	PROPOSED
GATE VALVE	⊗	⊗
FIRE HYDRANT	⊙	⊙
STOP BOX AND VALVE	⊙	⊙
FDC CONNECTION	➤	➤
WATER METER	●	
POST INDICATOR VALVE	■	
WELL HEAD	●	
IRRIGATION CONTROL BOX	■	
LAWN IRRIGATION HEAD	+	
GAS VALVE	⊗	
GAS MANHOLE	▲	
GAS RISER	⊗	
GAS METER	⊗	
ELECTRIC MANHOLE	⊗	
ELECTRIC RISER	▲	
ELECTRIC METER	⊗	
ELECTRIC TRANSFORMER	⊗	
LIGHT POLE	⊗	⊗
TELEPHONE MANHOLE	⊗	
TELEPHONE RISER	▲	
TELEPHONE CROSS BOX	⊗	
CABLE RISER	▲	
TRAFFIC CONTROL BOX	⊗	
AIR CONDITIONER	⊗	
PUBLIC LIGHTING MANHOLE	⊗	
UTILITY POLE	⊗	

	EXISTING	PROPOSED
GUY WIRE ANCHOR	<	
UTILITY FLAG	—	—
SIGN POST	—	—
GUARD POST/BOLLARD	⊙	●
FENCE POST	⊙	
PAY PHONE	⊗	
PARKING METER	⊗	
RESIDENTIAL MAILBOX	⊗	
U.S. MAILBOX	⊗	
BLDG CORNER (FIELD LOCATED)	★	
TREE	★	
WETLAND FLAG	★	
SPOT ELEVATION	±150.23	x xxx.xx
SOIL BORING	⬇	
ASPH.	ASPHALT	
CONC.	CONCRETE	
A.C.	AIR CONDITIONER	
G.P.	GUARD POST	
C.L.F.	CHAIN-LINK FENCE	
D.L.	DOOR LEDGE	
F.F.	FINISHED FLOOR	
O.H.	OVERHANG	
F.I.	FOUND IRON	
S.I.	SET IRON	
F.I.P.	FOUND IRON PIPE	
M. R.	MEASURED RECORD	
F.M.	FOUND MONUMENT	
S.N.	SET NAIL	



Engineers
Surveyors
Planners
Landscape Architects

28 West Adams Road
Suite 1200
Detroit, MI 48226
p (313) 962-4442
f (313) 962-5068
www.giffelswebster.com

Executive:	MWM
Manager:	RMJ
Designer:	AG/JH
Quality Control:	RMJ

Professional Seal:



Know what's below.
Call before you dig.

DATE:	ISSUE:
02-06-2023	30% DESIGN
02-27-2023	60% DESIGN
04-05-2023	90% DESIGN
----	----
----	----
----	----
----	----
----	----
----	----
----	----
----	----
----	----

Developed For:



330 TOWN CENTER DR, SUITE 1100
DEARBORN, MI 48126-2738



GENERAL NOTES
AND LEGEND

14TH STREET STREETScape
PHASE A

CITY OF DETROIT
WAYNE COUNTY
MICHIGAN


Date:	04.05.2023
Scale:	NO SCALE
Sheet:	C-002
Project:	19563.15D

Copyright © 2023 Giffels Webster.
No reproduction shall be made without the
prior written consent of Giffels Webster.



PRELIMINARY
NOT FOR CONSTRUCTION

V:\19563-120 Michigan Central Site\Design\CAD\14th St Streetscape\Worksheets\Phase A - Electronic Only\C-003 Alignment.dwg

PRELIMINARY
NOT FOR CONSTRUCTION



ROADWAY LINE DATA				
LINE #	DIRECTION	LENGTH	START	END
L1	S23°39'58"E	531.24'	N 304981.3107 E 13472489.7657	N 304494.7456 E 13472703.0098



**giffels
webster**

Engineers
Surveyors
Planners
Landscape Architects

28 West Adams Road
Suite 1200
Detroit, MI 48226
p (313) 962-4442
f (313) 962-5068
www.giffelswebster.com

Executive:	MWM
Manager:	RMJ
Designer:	AG/JH
Quality Control:	RMJ

Professional Seal:



DATE:	ISSUE:
02-06-2023	30% DESIGN
02-27-2023	60% DESIGN
04-05-2023	90% DESIGN
----	----
----	----
----	----
----	----
----	----
----	----
----	----
----	----
----	----

Developed For:



ALIGNMENT

14TH STREET STREETSCAPE
PHASE A

CITY OF DETROIT
WAYNE COUNTY
MICHIGAN

Date:	04.05.2023
Scale:	1"=30'
Sheet:	C-003
Project:	19563.15D

Copyright © 2023 Giffels Webster.
No reproduction shall be made without the
prior written consent of Giffels Webster.



Know what's below.
Call before you dig.

DATE:	ISSUE:
02-06-2023	30% DESIGN
02-27-2023	60% DESIGN
04-05-2023	90% DESIGN
----	----
----	----
----	----
----	----
----	----
----	----
----	----
----	----

Developed For:




TYPICAL CROSS SECTIONS


14TH STREET STREETSCAPE
PHASE A

CITY OF DETROIT
WAYNE COUNTY
MICHIGAN


Date:	04.05.2023
Scale:	1"=5'
Sheet:	C-004
Project:	19563.15D




EXISTING SECTION - 14TH STREET
STA 10+15 TO STA 11+99



EXISTING SECTION - 14TH STREET
STA 11+99 TO STA 15+15



PROPOSED SECTION - 14TH STREET
STA 10+15 TO STA 11+99



PROPOSED SECTION - 14TH STREET
STA 11+99 TO STA 15+15

No.	PAY ITEM	LEGEND
1	COLD MILLING HMA SURFACE	COLD MILL HMA SURFACE
2	SIDEWALK, REM	EXISTING PAVEMENT AND CURB
3	N.I.C PAVT, REM	CONCRETE PAVEMENT/SIDEWALK REMOVAL (INCLUDES CURB REMOVAL)
4	N.I.C TRACK, REM	HMA SURFACE
5	EXCAVATION, EARTH	CONCRETE PAVEMENT/SIDEWALK
1	HMA, 4EML	GRANULAR MATERIAL
2	HMA, 3EML	AGGREGATE BASE
3	GRANULAR MATERIAL, CLII	EXCAVATION, EARTH
4	AGGREGATE BASE, 6 INCH	
5	INTEGRAL CONCRETE CURB AND SIDEWALK	
6	HAND PATCHING, 4EML	
7	ELECTREON SYSTEM SEE JACOBS PLANS	
8	N.I.C HAND PATCHING, 4EML	
9	N.I.C AGGREGATE BASE	
10	N.I.C GRANULAR MATERIAL	



HMA APPLICATION TABLE

ITEM	APPLICATION RATE (LBS/SYD)	PERFORMANCE GRADE	NOTES	MINIMUM AWI
HMA 4EML	165	PG 64-22	4EML TOP COURSE (1.5-INCH LIFT)	220
HMA 3EML	220	PG 64-22	3EML LEVELING COURSE (2-INCH LIFT)	-
HAND PATCHING	165	PG 64-22	4EML TOP COURSE (1.5-INCH LIFT)	220
	220	PG 64-22	3EML LEVELING COURSE (2-INCH LIFT)	-

PRELIMINARY
NOT FOR CONSTRUCTION

14TH ST STREETSCAPE
SME CORING AND TEST PIT PLAN
11/08/2022

LEGEND
⊗ PAVEMENT CORE LOCATIONS - 3' DEEP (Staked by Giffels Webster)
[] TROLLEY TRACK TEST PIT - APPROX. 14' x 10' x 2' DEEP
RESTORE WITH COLD PATCH AND COMPACTED 21AA AGGREGATE



giffels
webster



PAVEMENT CORE LOG AND USACE DCP DATA

PROJECT NAME: Michigan Central Depot Streets Evaluation
PROJECT NO.: 085350.05
LOCATION: Detroit, Michigan
CLIENT: Giffels Webster Engineers, Inc.
STATION: A/E: GWE
DATE: 11/08/22
BY: ZALM


PROBECORE: RB194
STREET: 14th Street
LANE: Approx. Center of Roadway
STATION: A/E: GWE
DATE: 11/08/22
BY: ZALM

PAVEMENT AND SUBSURFACE CONDITIONS							
Layer, in.	From	To	Thickness, in.	Description	Comment		
0	3	3	3	Asphalt Concrete Pavement Wearing Course- Slight to Moderate Voids- Intact			
3	6	3	3	Asphalt Concrete Pavement Leveling Course- Moderate to Severe Voids- Intact			
6	12.5	6.5	6.5	Portland Cement Concrete- Slight to Severe Voids- Fractured- App. >1"			
12.5	22	9.5	9.5	FILL- Sandy LEAN CLAY with Sand- Brown- Very Stiff (CL)	@17" (Cap-3.0 ksf)(M.C.-18%)		
22	34	12	12	FILL- Fine SAND with Clay- Trace Gravel & Sand- Brown- Moist (SP-SC)	@38" (Cap-2.0 ksf)(M.C.-17%)		
34	51	17	17	LEAN CLAY with Sand- Trace Gravel- Brown- Stiff (CL)	@49" (Cap-1.1 ksf)(M.C.-18%)		

Depth to Groundwater From Ground Surface: None
Upon Completion: None

NOTES:
1. The indicated stratification layers are approximate. In situ, the transition between materials may be gradual.
2. Refer to Photolog for additional information.
3. Boring performed at location stated by GWE unless noted otherwise.

DCP TEST RESULTS									
Depth to start of test from ex. ground surface									
No. of Blows	Pen. (mm)	Blow Set (mm)	Pen./Blow Factor	Blow Factor	Depth from Surface (inches)	CBR (%)	Comment	Soil Type	Average CBR (%)
0	450	0	0	0	15.1	4.9	Poor	CL	7.8
3	540	80	27	1	15.1	12.5	Good	CL	
6	660	80	23	1	20.9	6.3	Marginal	CL	
3	740	80	27	1	24.0	4.9	Poor	SC	
3	810	70	23	1	26.8	6.3	Marginal	SC	
3	880	80	27	1	28.9	4.9	Poor	SC	
3	970	80	27	1	33.1	4.9	Poor	SC	5.4
1000	100	25	1	39.4	10.7	Good	CL	10.7	
4	1130	100	25	1	39.4	5.9	Marginal	CL	5.9



© 2022 SME

**Core picture shows approximate thickness



PAVEMENT CORE LOG AND USACE DCP DATA

PROJECT NAME: Michigan Central Depot Streets Evaluation
PROJECT NO.: 085350.05
LOCATION: Detroit, Michigan
CLIENT: Giffels Webster Engineers, Inc.
STATION: A/E: GWE
DATE: 11/08/22
BY: ZALM


PROBECORE: RB195
STREET: 14th Street
LANE: Approx. Center of Roadway
STATION: A/E: GWE
DATE: 11/08/22
BY: ZALM

PAVEMENT AND SUBSURFACE CONDITIONS							
Layer, in.	From	To	Thickness, in.	Description	Comment		
0	3	3	3	Asphalt Concrete Pavement Wearing Course- Slight to Moderate Voids- Vertical Cracking Underlain by 1/8-inch Thick Steel	Purposes of Steel Between Asphalt Layers Unknown		
3	8	5	5	Asphalt Concrete Pavement Leveling Course- Slight to Moderate Voids- Intact			
8	8.5	0.5	0.5	1/2-inch Thick Steel - Possible Rail			
8.5	10.1	1.6	1.6	1.6-Inch Thick Timber			
10.1	10.25	0.15	0.15	Unknown- DCP Attempted below Timber	Probe Terminated at Refusal		

Depth to Groundwater From Ground Surface: None
Upon Completion: None

NOTES:
1. The indicated stratification layers are approximate. In situ, the transition between materials may be gradual.
2. Refer to Photolog for additional information.
3. Boring performed at location stated by GWE unless noted otherwise.

DCP TEST RESULTS									
Depth to start of test from ex. ground surface									
No. of Blows	Pen. (mm)	Blow Set (mm)	Pen./Blow Factor	Blow Factor	Depth from Surface (inches)	CBR (%)	Comment	Soil Type	Average CBR (%)
0	360	0	0	0	1		Unknown		0
15	310	70	5	1	11.8	52.0	Poor	AGG BASE	
20	410	30	2	1	12.9	100.0	Good	AGG BASE	
10	410	5	1	1	13.1	100.0	Good	AGG BASE	
20	430	15	1	1	13.7	100.0	Good	AGG BASE	
20	450	20	1	1	14.2	100.0	Good	AGG BASE	
100	460	10	0	1	14.9	100.0	Good	AGG BASE	77.6



© 2022 SME

**Core picture shows approximate thickness



PAVEMENT CORE LOG AND USACE DCP DATA

PROJECT NAME: Michigan Central Depot Streets Evaluation
PROJECT NO.: 085350.05
LOCATION: Detroit, Michigan
CLIENT: Giffels Webster Engineers, Inc.
STATION: A/E: GWE
DATE: 11/08/22
BY: ZALM


PROBECORE: RB196
STREET: 14th Street
LANE: Approx. Center of Roadway
STATION: A/E: GWE
DATE: 11/08/22
BY: ZALM

PAVEMENT AND SUBSURFACE CONDITIONS							
Layer, in.	From	To	Thickness, in.	Description	Comment		
0	2	2	2	Asphalt Concrete Pavement Wearing Course- Slight to Moderate Voids- Delaminated and Shattered	Photo Not Provided Due to Shattered Section		
2	5	3	3	Asphalt Concrete Pavement Leveling Course- Slight to Severe Voids- Shattered	Photo Not Provided Due to Shattered Section		
5	20	15	15	AGGREGATE BASE- Dense-Graded CRUSHED CONCRETE			
20	30	10	10	FILL- LEAN CLAY with Sand- Gray- Very Stiff (CL)	@23" (Cap-2.25 ksf)(M.C.-17%)		
30	34	4	4	FILL- Sandy SILT- Trace Organic- Gray & Black- Moist (ML)			
34	43	9	9	FILL- LEAN CLAY with Sand & Organic- Gray & Black- Very Stiff (CL)	@38" (Cap-2.5 ksf)(M.C.-19%)		

Depth to Groundwater From Ground Surface: None
Upon Completion: None

NOTES:
1. The indicated stratification layers are approximate. In situ, the transition between materials may be gradual.
2. Refer to Photolog for additional information.
3. Boring performed at location stated by GWE unless noted otherwise.

DCP TEST RESULTS									
Depth to start of test from ex. ground surface									
No. of Blows	Pen. (mm)	Blow Set (mm)	Pen./Blow Factor	Blow Factor	Depth from Surface (inches)	CBR (%)	Comment	Soil Type	Average CBR (%)
0	310	0	0	0	11.8	52.0	Poor	AGG BASE	
15	360	70	5	1	12.9	100.0	Good	AGG BASE	
20	410	30	2	1	13.1	100.0	Good	AGG BASE	
10	410	5	1	1	13.7	100.0	Good	AGG BASE	
20	430	15	1	1	14.2	100.0	Good	AGG BASE	
20	450	20	1	1	14.9	100.0	Good	AGG BASE	
100	460	10	0	1	14.9	100.0	Good	AGG BASE	77.6



© 2022 SME

**Core picture shows approximate thickness



PAVEMENT CORE LOG AND USACE DCP DATA

PROJECT NAME: Michigan Central Depot Streets Evaluation
PROJECT NO.: 085350.05
LOCATION: Detroit, Michigan
CLIENT: Giffels Webster Engineers, Inc.
STATION: A/E: GWE
DATE: 11/08/22
BY: ZALM


PROBECORE: RB197
STREET: 14th Street
LANE: Approx. Center of Roadway
STATION: A/E: GWE
DATE: 11/08/22
BY: ZALM

PAVEMENT AND SUBSURFACE CONDITIONS							
Layer, in.	From	To	Thickness, in.	Description	Comment		
0	10	10	10	Asphalt Concrete Pavement Wearing Course- Shattered	Photo Not Provided Due to Shattered Section		
10	15	5	5	AGGREGATE BASE- CRUSHED LIMESTONE- Gray			
15	56	41	41	FILL- LEAN CLAY with Sand- Gray- Very Stiff (CL)	@17" (Cap-3.25 ksf)(M.C.-20%) @23" (Cap-2.25 ksf)(M.C.-19%) @37" (Cap-2.5 ksf)(M.C.-21%) @49" (Cap-2.75 ksf)(M.C.-18%)		

Depth to Groundwater From Ground Surface: None
Upon Completion: None

NOTES:
1. The indicated stratification layers are approximate. In situ, the transition between materials may be gradual.
2. Refer to Photolog for additional information.
3. Boring performed at location stated by GWE unless noted otherwise.

DCP TEST RESULTS									
Depth to start of test from ex. ground surface									
No. of Blows	Pen. (mm)	Blow Set (mm)	Pen./Blow Factor	Blow Factor	Depth from Surface (inches)	CBR (%)	Comment	Soil Type	Average CBR (%)
0	150	0	0	0	12.4	61.8	Marginal	AGG BASE	
15	410	60	4	1	14.7	61.8	Marginal	AGG BASE	
7	540	70	10	1	17.5	22.2	Very Poor	AGG BASE	38.2
3	610	70	23	1	22.2	4.3	Poor	CL	10.7
3	770	60	30	1	26.5	10.7	Good	CL	
2	800	50	1	1	28.9	3.8	Poor	CL	
2	900	70	35	1	31.7	2.8	Very Poor	CL	
2	980	80	40	1	34.8	2.2	Very Poor	CL	
2	1070	90	45	1	38.3	1.7	Very Poor	CL	2.4
2	1170	100	50	1	42.3	1.4	Very Poor	CL	



© 2022 SME

**Core picture shows approximate thickness

giffels
webster

Engineers
Surveyors
Planners
Landscape Architects

28 West Adams Road
Suite 1200
Detroit, MI 48226
p (313) 962-4442
f (313) 962-5088
www.giffelswebster.com

Executive: MWM
Manager: RMJ
Designer: AG/JH
Quality Control: RMJ

Professional Seal:



Know what's below.
Call before you dig.

DATE:	ISSUE:
02-06-2023	30% DESIGN
02-27-2023	60% DESIGN
04-05-2023	90% DESIGN
----	----
----	----
----	----
----	----
----	----
----	----
----	----
----	----

Developed For:



330 TOWN CENTER DR, SUITE 1100
DEARBORN, MI 48126-2738



SOIL BORING LOG

14TH STREET STREETSCAPE
PHASE A

CITY OF DETROIT
WAYNE COUNTY
MICHIGAN

Date: 04.05.2023
Scale: NO SCALE
Sheet: C-005
Project: 19563.15D

Copyright © 2023 Giffels Webster.
No reproduction shall be made without the
prior written consent of Giffels Webster.

PRELIMINARY
NOT FOR CONSTRUCTION

DEMOLITION QUANTITIES THIS SHEET

87	SYD	SIDEWALK, REM
2692	SYD	COLD MILLING HMA SURFACE
95	FT	CURB AND GUTTER, REM
51	CYD	EXCAVATION, EARTH

DEMOLITION NOTES

- 1 CURB AND GUTTER, REM
- 2 COLD MILLING HMA SURFACE
- 3 SIDEWALK, REM
- 4 N.I.C TRACK, REM
- 5 SHOWN FOR REFERENCE, WORK DONE BY OTHERS
- 6 EXCAVATION, EARTH

PROTECT-IN-PLACE NOTES

- 1 PROTECT-IN-PLACE EXISTING UTILITY POLE
- 2 PROTECT-IN-PLACE EXISTING HYDRANT
- 3 PROTECT-IN-PLACE GAS MAIN

DEMOLITION LEGEND

SIDEWALK, REM		CURB AND GUTTER, REM	
COLD MILLING HMA SURFACE		EXCAVATION, EARTH	
COLD MILLING HMA SURFACE OVER EXISTING TRACK			
REMOVALS BY OTHERS			

DEMOLITION PLAN

IMPROVEMENT QUANTITIES THIS SHEET

389	TON	HMA, 4EML
234	TON	HMA, 5EML
622	SFT	CURB RAMP, CONC, 6 INCH
48	FT	DETECTABLE WARNING SURFACE
95	FT	CURB RAMP OPENING, CONC
803	SFT	SIDEWALK, CONC, 4 INCH, INTEGRAL CURB

IMPROVEMENT PLAN NOTES

- 1 SIDEWALK, CONC, 4 INCH, INTEGRAL CURB
- 2 HMA - 1.5 INCH 5EML, ON 2.5 INCH 4EML
- 3 UTILITY TRENCH REMOVAL AND RESTORATION PER CITY OF DETROIT STANDARDS AND SPECIFICATIONS. SEE DETAIL ON SHEET C-500.
- 4 CAUTION: MULTIPLE GAS MAINS AND POSSIBLE VAULT IN THIS AREA. CONTRACTOR TO FIELD VERIFY LOCATIONS PRIOR TO PAVEMENT REMOVAL AND EXCAVATION.
- 5 MANAGEMENT UNIT AND ELECTRICAL HANDHOLE.
- 6 ELECTRICAL SYSTEM IN ROAD AND ASSOCIATED ELECTRICAL CONDUITS.
- 7 DTE CABINET BY OTHERS.
- 8 CURB RAMP, CONC, 6 INCH


- 9 CURB RAMP OPENING, CONC
- 10 DETECTABLE WARNING SURFACE

IMPROVEMENT PLAN LEGEND

MILL AND OVERLAY, 5EML 1.5 INCH ON 4EML INCH 3C		6" CONCRETE SIDEWALK PAVEMENT	
4" CONCRETE SIDEWALK PAVEMENT			
ELECTRICAL SYSTEM BY OTHERS			
FULL DEPTH ASPHALT PAVEMENT REPLACEMENT			
ELECTRICAL CONDUITS			
ELECTRICAL CONDUITS BY OTHERS			

IMPROVEMENT PLAN

NOTE: CONTRACTOR TO SCORE SIDEWALK 6" FROM FACE OF CURB TO PROVIDE A UNIFORM CURB JOINT



PRELIMINARY
NOT FOR CONSTRUCTION

giffels
webster

Engineers
Surveyors
Planners
Landscape Architects

28 West Adams Road
Suite 1200
Detroit, MI 48226
p (313) 962-4442
f (313) 962-5068
www.giffelswebster.com

Executive: MWM
Manager: RMJ
Designer: AG/JH
Quality Control: RMJ

Professional Seal:



Know what's below.
Call before you dig.

DATE:	ISSUE:
02-06-2023	30% DESIGN
02-27-2023	60% DESIGN
04-05-2023	90% DESIGN
----	----
----	----
----	----
----	----
----	----
----	----
----	----
----	----

Developed For:

FORDLAND
330 TOWN CENTER DR, SUITE 1100
DEARBORN, MI 48126-2738

DEMOLITION &
IMPROVEMENT PLAN

14TH STREET STREETSCAPE
PHASE A

CITY OF DETROIT
WAYNE COUNTY
MICHIGAN

Date: 04.05.2023
Scale: 1"=20'
Sheet: C-100
Project: 19563.15D

Copyright © 2023 Giffels Webster.
No reproduction shall be made without the
prior written consent of Giffels Webster.

Executive:	MWM
Manager:	RMJ
Designer:	AG/JH
Quality Control:	RMJ

Professional Seal:



Know what's below.
Call before you dig.

DATE:	ISSUE:
02-06-2023	30% DESIGN
02-27-2023	60% DESIGN
04-05-2023	90% DESIGN
----	----
----	----
----	----
----	----
----	----
----	----
----	----
----	----
----	----

Developed For:




PAVEMENT
MARKING AND
SIGNAGE PLAN


14TH STREET STREETSCAPE
PHASE A

CITY OF DETROIT
WAYNE COUNTY
MICHIGAN

Date:	04.05.2023
Scale:	1"=20'
Sheet:	C-200
Project:	19563.15D

Copyright © 2023 Giffels Webster.
No reproduction shall be made without the
prior written consent of Giffels Webster.





Developed For:

CITY OF DETROIT
WAYNE COUNTY
MICHIGAN

Copyright © 2022 Gilfils Webster.
No reproduction shall be made without the
prior written consent of Gilfils Webster.



SESC LEGEND AND QUANTITIES		
DESCRIPTION	LEGEND	QUANTITY
SEDIMENT INLET FILTER		2 EACH
LIMITS OF DISTURBANCE		0.56 AC

1 PROVIDE, INSTALL, AND MAINTAIN TEMPORARY SEDIMENT INLET FILTER. SEE DETAIL ON THIS SHEET.

2 PROPOSED LIMITS OF DISTURBANCE



Developed For:

CITY OF DETROIT
WAYNE COUNTY
MICHIGAN

Copyright © 2022 Giffels Webster.
No reproduction shall be made without the
prior written consent of Giffels Webster.




1. IF ANY OF THE EXISTING BASE CANNOT BE UTILIZED, IT SHALL BE REMOVED AND REPLACED WITH MDOT CLASS II MATERIAL.
2. BROOM FINISH SURFACE
3. IF NOT INDICATED ON THE PLANS THE CONTRACTOR SHALL SUBMIT A JOINTING PLAN PRIOR TO PLACEMENT OF CONCRETE PAVEMENT.
4. SAWCUT JOINTS AS SOON AS PAVEMENT CAN SUPPORT MACHINE.
5. PLACE EXPANSION JOINT BETWEEN NEW WALKS AND EXISTING PAVEMENT AND/OR BUILDINGS.

NOT TO SCALE








PRELIMINARY
NOT FOR CONSTRUCTION



HMA SURFACE ON
CONCRETE BASE
UTILITY TRENCH
CONSTRUCTION
PAVEMENT RESTORATION

CITY OF DETROIT
CITY ENGINEERING DIVISION
SURVEY BUREAU
JOB NO.
DRAWG. NO. 2 OF 2











8 West Adams Road
Suite 1200
Detroit, MI 48226
p (313) 962-4442
f (313) 962-5068
www.giffelswebster.com

Executive:	MWM
Manager:	RMJ
Designer:	AG/JH
Quality Control:	RMJ

Professional Seal:



- | | |
|---|-------------------|
|  | DETOUR ROUTE |
|  | BARRICADE |
|  | TEMPORARY SIGN |
|  | LANE CLOSURE AREA |
|  | PLASTIC DRUM |

[illegible]

Developed For:



14TH ST MOT

14TH STREET STREETSCAPE
PHASE A


CITY OF DETROIT
WAYNE COUNTY
MICHIGAN

Date:	04.05.2023
Scale:	1"=100'
Sheet:	T-100
Project:	19563.15D

Copyright © 2022 Giffels Webster.
 reproduction shall be made without the
 or written consent of Giffels Webster.

V:\19563-12D Michigan Central Site\Design\CAD\14th St Streetscape\Exhibits\MOT.dwg




V:\19563-12D Michigan Central Site\Design\CAD\14th St Streetscape\Exhibit\MOT.dwg



LOCATION MAP / KEY MAP
(NOT TO SCALE)

LEGEND

- DETOUR ROUTE
- BARRICADE
- TEMPORARY SIGN
- LANE CLOSURE AREA
- PLASTIC DRUM



Executive:	MWM
Manager:	RMJ
Designer:	AG/JH
Quality Control:	RMJ

Professional Seal:



DATE:	ISSUE:
30% DESIGN	02-06-2023
60% DESIGN	02-24-2023
90% DESIGN	04-05-2023
---	---
---	---
---	---
---	---
---	---
---	---
---	---
---	---

Developed For:



14TH ST MOT

14TH STREET STREETScape
PHASE A

CITY OF DETROIT
WAYNE COUNTY
MICHIGAN

Date:	04.05.2023
Scale:	1"=150'
Sheet:	T-101
Project:	19563.15D

THE IMPROVEMENTS COVERED BY THESE PLANS SHALL BE DONE IN ACCORDANCE WITH THE MICHIGAN DEPARTMENT OF TRANSPORTATION 2020 STANDARD SPECIFICATIONS FOR CONSTRUCTION.

PHYSICAL ROAD NUMBER (PR#) & MILEPOST (MP) DATA ARE FROM MICHIGAN GEOGRAPHIC FRAMEWORK VERSION # .

TRAFFIC DATA				SPEED DATA	
ROAD	YEAR	ADT	COMM	DESIGN	POSTED
14TH STREET	2021	700	5%	30 MPH	30 MPH

GENERAL PROVISIONS

ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE APPROVED PLANS, THE 2020 MICHIGAN DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR CONSTRUCTION AND THE 2011 MICHIGAN MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES.

ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE MAINTENANCE OF TRAFFIC PLAN AND AASHTO POLICY ON GEOMETRIC DESIGN OF HIGHWAYS AND STREETS, 2018 EDITION.

UTILITY STATEMENT

THE UNDERGROUND UTILITIES SHOWN HAVE BEEN LOCATED FROM FIELD SURVEY, INFORMATION AND EXISTING DRAWINGS. THE SURVEYOR MAKES NO GUARANTEES THAT TEH UNDERGROUND UTILITIES SHOWN COMPRISE ALL SUCH UTILITIES IN THE AREA. EITHER IN SERVICE OR ABANDONED. THE SURVEYOR FURHTER DOE NOT WARRENT THAT THE UNDGERGROUND UTILITIES SHOWN ARE TEH EXACT LOCATION INDICATED ALTHOUGH HE DOES CERTIFY THAT THEY ARE LOCATED AS ACCURATELY AS POSSIBLE FROM INFORMATION AVAILABLE.

(R) = UTILITY SHOWN FROM RECORDS OR PLANS, & FIELD LOCATED WHERE POSSIBLE.

MICHIGAN DEPARTMENT OF TRANSPORTATION

IN COOPERATION WITH

MICHIGAN CENTRAL AND THE CITY OF DETROIT


INDUCTIVE VEHICLE CHARGING PILOT

14TH STREET STREETSCAPE - PHASE A

PLAN 2

CITY OF DETROIT

WAYNE COUNTY



WAYNE
COUNTY

COUNTY KEY



JN 20900
POB STA 10+22.50
POE STA 15+18.50



LOCATION MAP

NO SCALE

90% REVIEW SET

MICHIGAN
DEPARTMENT OF TRANSPORTATION

BRAD WIEFERICH, P.E. - ACTING DIRECTOR

MILES:
CONTRACT FOR:

FINAL ROW PLAN REVISIONS				SUBMITTAL DATE:			
NO.	DATE	AUTH	DESCRIPTION	NO.	DATE	AUTH	DESCRIPTION



NO SCALE

FILE: 20900_TITLE_001.dgn

DATE: APRIL 2023

DESIGN UNIT:

TSC: 213305

CS:

JN:

TITLE SHEET		DRAWING	SHEET
INDUCTIVE VEHICLE CHARGING PILOT		14TH ST TITLE	SECT 1
14TH STREET STREETSCAPE PHASE A - PLAN 2		001	1

PUBLIC UTILITIES

The existing utilities listed below and shown on these plans represent the best information available as obtained on our surveys. This information does not relieve the contractor of the responsibility to be satisfied as to it's accuracy and the location of existing utilities.

<u>Name Of Owner</u>	<u>Type Of Utility</u>
----------------------	------------------------

Public Lighting Authority of Detroit Street Lighting
Attention: Mukesh Patel
65 Cadillac Square, Suite 3100
Detroit, MI 48226
Phone: 313.324.8290
Email: mpatel@pladetroit.org

City of Detroit
 Detroit Water & Sewerage Department
 6425 Huber
 Detroit, MI 48211
 Syed Ali: 313.267.8309
 Email: syed.ali@detroitmi.gov
 Emergency: 313.267.1333

City of Detroit
Traffic Engineering Division – DPW
 Attention: Prasad Nannapaneni
 2633 Michigan Avenue
 Detroit, MI 48207
 Phone: 313.628.5603
 Fax: 313.224.1304
 Email: prasadn@detroitmi.gov
 Meena Antani: 313.628.5640
 Email: antanim@detroitmi.gov

Pavement Markings,
 Signs & Traffic Signals

Sign Shop
2425 Fenkell
Detroit, MI 48238
Phone: 313.628.2950
Fax: 313.628.4966

City of Detroit
Detroit Fire Department
Detroit Public Safety Headquarters
Fire Marshal's Division & Fire Prevention
1301 Third St.
Detroit, MI 48226
Plan Review: 313.224.3233
Chief Robinson: 313.596.2788
Fax: 313.224.4128

City of Detroit
Detroit Police Department
Department of Public Safety Headquarters
1301 Third Street
Detroit, MI 48226
Phone: 313.596.2520

DTE / Detroit Edison Electric power
Attention: Robin O'Connell
1 Energy Plaza
IGS Group, 518SB
Detroit, MI 48226
Phone: 313.235.5632
Fax: 313.235.9366
Phone: 313.237.9567

<u>Name Of Owner</u>	<u>Type Of Utility</u>
----------------------	------------------------

DTE / Michigan Consolidated Gas Company Gas Mains
Attention: Tim Stoian
500 Griswold Sr
Detroit, MI 48226
Phone: 734.660.8716
Email: timothy.stoian@dteenergy.com
Kevin Price: 313.600.1884
Barbara Saunders: 313.577.7435
Fax: 313.577.7498
Phone: 1.800.477.4747

AT&T Metro East	Telephone
Attention: Joe Sikoski	
100 S Main St, Suite 314	
Mt. Clemens, MI 48043-2374	
Phone: 586.466.6310	

AT&T Metro West
 Attention: John Crispin
 31100 Plymouth Rd, Room 301
 Livonia, MI 48150-2104
 Phone: 734.523.6880



For Adjusting Frames
 and Covers

Detroit Thermal LLC Steam Lines
Attention: Ed LaRosa
3575 E Palmer St
Detroit, MI 48201
Phone: 313.921.1922
Fax: 313.921.1972
Emergencies: 313.963.3707

Comcast Cablevision TV Cables
Attention: Glen Younglove
25626 Telegraph Rd
Southfield, MI 48034
Phone: 248.809.2712
Fax: 248.809.2721
Email: Glen_Younglove@cable.comcast.com

SHEET INDEX

Section 1 - Road Plans	
Title	1
Project Information	2
Legend	3 – 4
Notes	5
Typical Cross Sections	6
Dynamic Management Unit Schematics	7
APFC Cabinet Schematics	8
Survey Information	9
Site Plan	10
Dynamic Unit One-Line Diagram	11
Electrical Riser Diagram	12
Electrical Details	13

FINAL ROW PLAN REVISIONS (SUBMITTAL DATE:)										NO SCALE		DATE: APRIL 2023	CS:	PROJECT INFORMATION SHEET	DRAWING	SHEET
NO.	DATE	AUTH	DESCRIPTION	NO.	DATE	AUTH	DESCRIPTION					DESIGN UNIT:	JN:	INDUCTIVE VEHICLE CHARGING PILOT	14TH ST. PROJ 001	SECT 1
											FILE: 20900_Project Information_001.doc	TSC: 213305		14TH STREET STREETScape PHASE A – PLAN 2	2	

UTILITIES

COMBINED SEWER

-)→)→)→)→)→) COMBINED SEWER
-)↯→)↯→)↯→)↯ COMBINED SEWER - OUT OF SERVICE
-)●→)●→)●→)●→)●→) COMBINED SEWER - TO BE TAKEN OUT OF SERVICE
-)✕→)✕→)✕→)✕→)✕→) COMBINED SEWER - TO BE REMOVED

COMMUNICATION

- F0 —— FIBER OPTIC
- ↯↯ F0 ↯↯ FIBER OPTIC - OUT OF SERVICE
- F0-OH —— FIBER OPTIC - OVERHEAD
- ⓘ FIBER OPTIC MARKER
- C —— CABLE
- ↯↯ C ↯↯ CABLE - OUT OF SERVICE
- C-OH —— CABLE - OVERHEAD
- ⓘ CABLE MARKER
- ◇ CABLE PEDESTAL
- T —— TELEPHONE
- ↯↯ T ↯↯ TELEPHONE - OUT OF SERVICE
- T-OH —— TELEPHONE - OVERHEAD
- ☐ TELEPHONE BOX
- ⓘ TELEPHONE MANHOLE
- ◇ TELEPHONE PEDESTAL

FUEL / PETROLEUM

- ⊖ GASOLINE FILLER PIPE
- ⛽ GASOLINE PUMP
- ⬭ GASOLINE UNDERGROUND TANK
- PETRO —— PETROLEUM PIPELINE
- ↯↯ PETRO ↯↯ PETROLEUM PIPELINE - OUT OF SERVICE
- ⓘ PETROLEUM PIPELINE MARKER
- Ⓟ PETROLEUM WELL
- Ⓟ PROPANE TANK

NATURAL GAS

- G —— GAS LINE
- ↯↯ G ↯↯ GAS LINE - OUT OF SERVICE
- ⓘ MARKER
- ⌛ VALVE
- ⌚ WELL

SANITARY SEWER

- Ⓢ MANHOLE WITH COVER (DIA VARIES)
-)——)——)——) SEWER
- ↯——↯——↯——↯ SEWER - OUT OF SERVICE
- SEWER - TO BE TAKEN OUT OF SERVICE
- ✕——✕——✕——✕ SEWER - TO BE REMOVED

WATER

- ⚡ FIRE HYDRANT
- ⊗ GATE VALVE AND BOX
- Ⓜ GATE VALVE IN WELL
- ⚡ IRRIGATION CONTROL VALVE
- ⚡ IRRIGATION SPRINKLER HEAD
- ⌚ SERVICE METER
- ⊖ SERVICE SHUTOFF
- Ⓢ WATER WELL
- I —— IRRIGATION
- W —— WATER MAIN
- ↯↯ W ↯↯ WATER MAIN - OUT OF SERVICE
- W ——●—— W WATER MAIN - TO BE TAKEN OUT OF SERVICE
- ✕—— W ——✕—— W WATER MAIN - TO BE REMOVED

STEAM

- STEAM —— STEAM
- ↯↯ STEAM ↯↯ STEAM - OUT OF SERVICE

GENERIC EXISTING UTILITIES

- Ⓢ ☐ CATCH BASIN COVER
- MANHOLE COVER
- ⓘ MARKER
- Ⓢ PEDESTAL
- Ⓢ SEWER CLEANOUT ACCESS
- STRUCTURE BOTTOM (DIA VARIES)
- ⌚ UTILITY BOX
- U —— UTILITY

DRAINAGE

- Ⓢ Ⓢ Ⓢ CATCH BASIN W/ COVER (DIA VARIES)
- 12 DRAINAGE STRUCTURE NUMBER
- DRAIN CASTING
- DROP INLET
- ▷ ▷ ▷ ▷ END SECTION (SIZE VARIES)
- FLOW DIRECTION ARROW
- ⌚ HEADWALL (SIZE VARIES)
- Ⓢ MANHOLE W/ COVER (DIA VARIES)
- Ⓢ MANHOLE BASE W/ COVER (SIZE VARIES)
- Ⓢ MANHOLE TEE W/ COVER (SIZE VARIES)
- ⌚ OUTLET HEADWALL (SIZE VARIES)
- CULVERT - EXISTING
- ▬ CULVERT (SIZE VARIES)
- ⋯ DITCH CENTERLINE
- ▷ ▷ ▷ ▷ STORM SEWER - EXISTING
- → → → STORM SEWER
- ✕ ▷ ✕ ▷ ✕ ▷ ✕ STORM SEWER - TO BE REMOVED
- → → → UNDERDRAIN
- ⋯ WATER EDGE

NOTE:

EXISTING ITEMS ARE REPRESENTED BY THIN LINE WEIGHTS ON SITE PLAN.

PROPOSED ITEMS ARE REPRESENTED BY HEAVIER LINE WEIGHTS ON SITE PLAN.

GENERAL NOTES & SPECIFICATIONS

UTILITIES

MISS DIG/UNDERGROUND UTILITY NOTIFICATION

Contact MISS DIG System, Inc. for the protection of underground utilities and in conformance with MCL 460.721 et seq, by phone at 811 or 800-482-7171 or via the web at missdig811.org, a minimum of 3 working days prior to excavating, excluding weekends and holidays.

SURVEY

PRESERVATION OF BOUNDARY MONUMENTS

Preserve all corners within the project limits, whether shown or not. Adjust monument boxes as required.

PROJECT SPECIFIC NOTES

CONTROLLED LOW STRENGTH MATERIAL (CLSM)

DESCRIPTION

The work consists of mixing and placing Controlled Low Strength Material (CLSM) without slag at the locations shown on the Contract Drawings or where ordered by the Engineer.

MATERIALS

A. General

CLSM shall be a mixture of portland cement, aggregate, fly ash, water, and admixtures that forms a workable, flowable slurry mix that is non-segregating, self-consolidating, and nonshrink with a compressive strength of at least 750 PSI to 1000 PSI at 28 days in accordance with ASTM D4832. Prepare CLSM in accordance with ASTM C94. The use of slag and recycled materials shall not be permitted.

- 1. Processed Aggregate: ASTM C33/33M, 100 percent passing 3/8inch sieve; 75 percent to 100 percent passing No. 4 sieve; 12 percent to 50 percent passing No. 30 sieve; 5 percent to 20 percent passing No. 100 sieve; and under 10 percent nonplastic fines.
- 2. Soluble sulfate shall be under 0.3 percent.
- 3. Up to 300Pounds per Cubic Yard Fly Ash (Pozzolan): ASTM C618, Class C.
- 4. Water: Clean, potable, containing less than 500 ppm of chlorides.
- 5. Submit for approval prior to use, a complete mix design. The minimum submittal contents shall include but is not limited to the following.
 - A. Mix summary showing volume and weight per cubic yard for each proposed constituent.
 - B. Design 28-day compressive strength, slump, air content, water-cement ratio and density.
 - C. Certified test results from an Independent Testing Agency for: Cement, supplementary cementitious materials, and aggregates that document the proposed materials meet the required ASTM standards.
 - D. Combined aggregate gradation by sieve.
 - E. Manufacturer's datasheets for each proposed admixture.
 - F. Letter from the admixture manufacturer that the proposed admixtures are compatible.
 - G. Additional documentation and testing materials required by the Engineer.

Batching equipment shall be accurate and demonstrate components remain within plus or minus 2percent of design mix. Volumetric batching may be used if it provides same weight accuracy. Design and operate mixers so discharged CLSM have same consistency

through each batch and so temperature stays between 50 degrees F and 90 degrees F. Do not add water after batching. Batch to placement time shall not exceed 120 minutes.

B. Tests and Control Methods

Contractor shall provide the mix design for review and certification from an approved testing laboratory that the CLSM will have a 28-day compressive strength between 750 PSI and 1000 PSI shall be furnished by the Contractor and provided to the Engineer prior to delivery of any materials.

The CLSM shall have a minimum diameter spread of 8 in. as determined by the following procedure to be performed by the Engineer:

- Fill a hollow plastic or metal cylinder 8 in. in length and 3 in. inside diameter with the CLSM and strike off the surface. Raise the flow cylinder in a continuous motion without rotation.
- Immediately measure the spread of the CLSM along two diameters which are perpendicular to each other.

The Contractor shall cast four (4) specimens (cylinders) for each batch in accordance and deliver them to an approved Material Testing Laboratory within seven days of the pour date for evaluation.

For each 50 Cubic Yard or portion thereof, the following Field Testing shall be performed to confirm the material conformance with the approved design mix:

ASTM D 6023	Unit Weight, Yield Cement Content & Air Content
ASTM D 5971	Sampling Freshly Mixed CLSM
ASTM D 4832	Preparation and Testing of CLSM
ASTM D 6103	Flow Consistency of CLSM

Prior to proceeding with subsequent construction operations, either one of the following Field Tests shall be performed on the surface of the in-place CLSM to estimate its surface bearing value and its suitability for load application.

ASTM D 6024	Ball Drop on CLSM
ASTM D 3441	Cone and Friction Cone Penetration Tests

A minimum of three (3) tests shall be performed for each 200 Square Feet or portion thereof, and evaluated against the following criteria:

ASTM D 6024	Inspect the indentations for visible water or sheen brought to the surface by the dropping action of the ball.
-------------	--

If the diameter of the indentation is equal or less than 3 inches, than the CLSM is suitable for load application, provided that:

- a. The surface looks similar to that before the test with the exception of the indentation, and;
- b. There is no visible surface water or sheen visible in the indentation.

ASTM D 3441	The average value of the three (3) tests shall be not less than Four (4) Tons/Square Foot. The minimum value per individual test shall not be less than Three (3) Tons/Square Foot.
-------------	---

CONSTRUCTION DETAILS

A. General

The Contractor shall provide all equipment for this work subject to approval of the Engineer. Mix the materials at a stationary mixing plant which is either a continuous or a batch type plant, designed to accurately proportion either by volume or by weight, so that when the materials are incorporated in the mix, a thorough and uniform mix will result.

The mix may be transported in open haul units provided the material is placed within 30 minutes of the end of mixing. Use a rotating drum unit capable of 2 - 6 rpm to transport material that cannot be placed within 30 minutes after the end of mixing. In cases where placement cannot take place within 30 minutes from the end of mixing, the material shall be transported in a rotating drum capable of 2 – 6 rpm.

Provide a mixer capable of mixing CLSM that has the specified compressive strength and flow consistency. Mix all components so as

to produce a uniform product. For work involving CLSM quantities of less than two (2) cubic yards, the Engineer may permit the Contractor to use a small construction mixer.

Narrower trench widths can be employed when using CLSM due to the self-compacting properties of the material. Construction personnel and equipment are not required to be in the trench for compaction operations.

For installations that require construction personnel to temporarily occupy the trench, the Contractor shall follow all OSHA requirements.

B. Fill and backfill at structures, culverts, pipes, conduits and direct burial cables.

The Contractor shall place the CLSM using a method approved by the Engineer, in accordance with the appropriate MDOT guidance on the use of CLSM as backfill material.

When placing CLSM for pipe backfill, discharge the material onto the top of the pipe at the center.

Do not place CLSM in contact with aluminum pipe, including connections, fixtures, etc., unless the aluminum has been coated with an approved primer.

MEASUREMENT

The quantity to be measured for payment shall be the number of cubic yards of satisfactorily placed CLSM computed between the payment lines shown on the Contract Documents or from payment lines established in writing by the Engineer.

Cross sectioning, for the purpose of determining quantities for payment, shall be employed only where payment lines are not shown on the Contract Drawings, and cannot be reasonably established by the Engineer.

PRICE TO COVER

The unit price bid per cubic yard of CLSM shall include the costs of furnishing all labor, materials, equipment, insurance, and incidentals necessary to complete the work, except where specific costs are designated or included in another pay item of work. The unit price also includes any temporary supports for the exposed utilities which will be encapsulated in the CLSM.

Payment will be made under:		
Item		Pay Unit
CONTROLLED LOW STRENGTH MATERIAL		C.Y.

SEQUENCE OF CONSTRUCTION

STEP 1 – SITE PREPARATION

- A. Contractor shall remove existing pavement as directed in the plans.
- B. Contractor shall install all conduits per plans and as directed by the Engineer.
- C. Contractor shall ensure all conduits have a temporary cap on both ends.
- D. Contractor shall install Management Unit (MU) and APFC base slabs per drawings and specifications.
- E. Contractor shall install aggregate base for pavement section.
- F. Contractor shall pave a 2.5in leveling course layer of asphalt as per the specifications. The leveling course shall extend the width of the full depth pavement removal section.

STEP 2 – CABINET INSTALLATION (APFC AND MU)

Electreon will be on site to assist and guide contractor.

- A. Contractor shall install cabinets on the base slabs.
 - I. MU is lifted from the bottom of the cabinet
 - II. APFC is lifted from the top of the cabinet
- B. Contractor shall install wiring through the conduits.

- C. Contractor shall install the wires in the cabinets.
- D. Contractor shall connect the APFC Cabinet to the grid and confirm connection is energized.

STEP 3 – TRENCH EXCAVATION

- C. Contractor shall perform a pavement sawcut through the 2.5" leveling course to create a clean edge for the charging segment.
- D. Contractor shall remove aggregate and leveling course to create the trench.

Note: Steps 4 through 6 shall be completed within one working day. Weather conditions shall be dry for the entire period.

STEP 4 - INSTALLATION OF WIRING IN TRENCH

- A. Contractor shall remove caps on 3" conduits.
- B. Contractor shall pull wiring and cables through the 3" conduits per the direction of Electreon.
- C. Electreon shall connect the cables to the charging system.
- D. Electreon shall complete testing of the system within 2 hours.

STEP 5 - FILLING OF THE TRENCH

- A. After testing is complete, the contractor shall immediately backfill the trench with controlled low-strength material (CLSM) as per specifications and allow to cure for a minimum of 2 hours.

STEP 6 – HMA CONSTRUCTION

- A. Immediately after CLSM curing period is complete, contractor shall install MDOT 2C HMA. Contractor shall use a tandem steel roller with static drums for the first two compaction passes over the charger coil segments. After the first two passes, the contractor may use a tandem steel roller with vibratory drums to meet MDOT compaction specifications.
- B. Contractor shall install and compact MDOT 4C HMA per Construction and Material Specifications.

STEP 7 – POST INSTALLATION TEST

- A. Electreon shall perform post-installation testing once the MDOT 4C HMA installation is completed and traffic is permitted to drive on the HMA.

STEP 8 – TRAFFIC CONTROL

- A. Contractor shall install pavement markings and signs. Refer to Plan 2 for layout and details.

STEP 9 – FINAL TESTING


- A. Electreon shall perform system testing after traffic control is installed.





Management Unit, Installed

The contractor shall install the Management Units supplied and delivered to the site by Electreon. The contractor shall be responsible for off-loading and storing the Management Units prior to installation. The contractor shall install the Management Units per the plans and as directed by the engineer. All costs associated with handling, storage and installation shall be included in Item Management Unit, Installed.


Active APFC Cabinet, Installed

The contractor shall install the Active PFC Cabinet supplied and delivered to the site by Electreon. The contractor shall be responsible for off-loading and storing the Active PFC Cabinet prior to installation. The contractor shall install the Active PFC Cabinet per the plans and as directed by the engineer. All costs associated with handling, storage and installation shall be included in Item Active PFC Cabinet, Installed.


FINAL ROW PLAN REVISIONS (SUBMITTAL DATE:)								<div>Jacobs electreon</div>	<div> Michigan Department of Transportation</div>	NO SCALE		DATE: APRIL 2023	CS:	NOTE SHEET	DRAWING	SHEET
NO.	DATE	AUTH	DESCRIPTION	NO.	DATE	AUTH	DESCRIPTION					DESIGN UNIT:	JN:	INDUCTIVE VEHICLE CHARGING PILOT	14TH ST. NOTE	SECT 1
												FILE: 20900_Note_001.doc	TSC: 213305		001	5
														14TH STREET STREETScape PHASE A – PLAN 2		



NOTES:
1. MAINTAIN 36" CLEARANCE FOR ACCESS TO MANAGEMENT UNIT DOORS.



APFC CABINET
SIDE VIEW 1



APFC CABINET
PLAN VIEW A-A

NOTES

COORDINATE SYSTEM: STATE PLANE GRID
ZONE: MICHIGAN SOUTH 2113
ELLIPSOID: GRS 80
HORIZONTAL DATUM: NAD 83 (2007)
VERTICAL DATUM: NAVD 88
GEOID: GEOID 09
UNITS: INTERNATIONAL FEET

GROUND DISTANCE CONVERSION

THE COMBINED SCALE FACTOR (CSF) FOR EACH CONTROL POINT
IS INCLUDED IN THE CONTROL POINT LIST.

AVERAGE COMBINED SCALE FACTOR (ACSF) = (CSF1 + CSF2)/2
GROUND DISTANCE = GRID DISTANCE / ACSF

SEE PLAN SET 1 FOR ADDITIONAL INFORMATION.


QUANTITIES THIS SHEET:

JN 20900
CAT 0001

- 525 FT #600KCMIL TYPE RHHW COPPER WIRE
- 1500 FT #500KCMIL TYPE RHHW COPPER WIRE
- 175 FT #4/0 AWG TYPE RHHW COPPER WIRE
- 500 FT #3 AWG TYPE RHHW COPPER WIRE
- 1500 FT #10 AWG TYPE RHHW COPPER WIRE
- 50 FT 4" RIGID GALVANIZED STEEL CONDUIT
- 15 FT 3" RIGID GALVANIZED STEEL CONDUIT
- 25 FT 1" RIGID GALVANIZED STEEL CONDUIT
- 505 FT 4" PVC SCHEDULE 80 CONDUIT
- 500 FT 3" PVC SCHEDULE 80 CONDUIT
- 1000 FT 1" PVC SCHEDULE 80 CONDUIT
- 1200 FT ETHERNET CAT6 CABLING
- 2 EACH 4" EXPANSION/DEFLECTION FITTING
- 3 EACH #500KCMIL POLARIS SUBMERSIBLE SPLICE BLOCK
- 3 EACH #10 AWG POLARIS SUBMERSIBLE SPLICE BLOCK
- 4 EACH 3/4" x 10" GROUND ROD
- 3 EACH ELECTRICAL HANDHOLE
- 1 EACH 400A SERVICE ENTRANCE RATED DISCONNECT
- 1 EACH 400A COMBINATION CT/UTILITY METER CABINET
- 3 EACH MANAGEMENT UNIT, INSTALLED
- 1 EACH ACTIVE PFC UNIT, INSTALLED

JN 20900
CAT 0001

- 7197 SYD PAVT, REM
- 1021 FT PAVT SAWCUT
- 23 CYD EXCAVATION, EARTH
- 82 TON HMA, 3C
- 5 CYD CONTROLLED LOW STRENGTH MATERIAL (CLSM)
- 23 CYD GRANULAR MATERIAL
- 442 TON AGGREGATE BASE
- 1 CYD CONCRETE
- 4 EACH SIDEWALK SECTIONS, REM




FINAL ROW PLAN REVISIONS				SUBMITTAL DATE:			
NO.	DATE	AUTH	DESCRIPTION	NO.	DATE	AUTH	DESCRIPTION




FILE: 20900_PLANS_001.DGN	DATE: APRIL 2023
	DESIGN UNIT:
	TSC: 213305

CS:
JN:


SITE PLAN	
INDUCTIVE VEHICLE CHARGING PILOT	
14TH STREET STREETSCAPE PHASE A - PLAN 2	
DRAWING 14 ST. SITE PLAN 001	SHEET SECT 1 10




DYNAMIC UNIT ONE - LINE DIAGRAM
NTS



DYNAMIC UNIT ELECTRICAL RISER DIAGRAM
NTS




2605-008b



2605-235

1. PROVIDE THE WORK IN ACCORDANCE WITH NFPA 70, WHERE REQUIRED BY AUTHORITY HAVING JURISDICTION (AHJ). MATERIAL AND EQUIPMENT SHALL BE LABELED OR LISTED BY A NATIONALLY RECOGNIZED TESTING LABORATORY OR OTHER ORGANIZATION ACCEPTABLE TO THE AHJ, IN ORDER TO PROVIDE UBASIS FOR APPROVAL UNDER THE NEC.
2. ELECTRICAL DRAWINGS SHOW GENERAL LOCATIONS OF EQUIPMENT, DEVICES, AND RACEWAY, UNLESS SPECIFICALLY DIMENSIONED. CONTRACTOR SHALL BE RESPONSIBLE FOR ACTUAL LOCATION OF EQUIPMENT AND DEVICES AND FOR PROPER ROUTING AND SUPPORT OF RACEWAYS, SUBJECT TO APPROVAL OF ENGINEER.
3. SUBMITTALS: PROVIDE PRODUCT DATA FOR WIRE, CONDUIT, AND ALL ACCESSORIES ASSOCIATED WITH THE ELECTRICAL INSTALLATION.
4. CONDUCTORS: SHALL CONFORM TO APPLICABLE REQUIREMENTS OF NEMA WC70. CABLE SHALL BE STRANDED COPPER/UND TYPE RHHW. CABLES SHALL BE RATED FOR 600V AC RMS. CABLES SHALL BE BY SOUTHWIRE, OR APPROVED EQUAL.
5. PULLING COMPOUND FOR CABLES SHALL BE NON-TOXIC, NON-CORROSIVE, WATER BASED LUBRICANT AND SHALL BE APPROVED FOR THE INTENDED USE BY THE CABLE MANUFACTURER.
6. CONDUITS: RIGID GALVANIZED STEEL CONDUIT SHALL MEET THE REQUIREMENTS OF NEMA C80.1 AND UL 6. PVC SCHEDULE 80 CONDUIT SHALL MEET THE REQUIREMENTS OF NEMA TC2 AND UL 651. PROVIDE ALL FITTINGS AND ACCESSORIES, AS NECESSARY, TO COMPLETE THE CONDUIT SYSTEM AS SHOWN ON THE DRAWINGS.
7. WHEN TRANSITIONING FROM PVC SCHEDULE 80 TO RIGID GALVANIZED CONDUIT, USE PVC-COATED RIGID GALVANIZED STEEL.
8. PROVIDE A SHORT CIRCUIT STUDY AND ARC FLASH STUDY OF THE ELECTRICAL SYSTEM. STUDIES SHALL BE PREPARED BY PROFESSIONAL ENGINEER REGISTERED IN THE STATE OF MICHIGAN. PROVIDE ARC FLASH LABELING, AS REQUIRED.



Jacobs
electreon

 **MDOT**
Michigan Department of Transportation

FILE: 20900_ELEC-DET_003.DGN

TSC: 213305

DRAWING	SHEET
14TH ST. PLAN 003	SECT 1 13